

**All Information Completely
Required Affidavit
1 or Deliver Report to:
Conservation Division
State Corporation Commission
200 Bittig Building
Wichita, Kansas**

Sec. 13

Locate well correctly on above
Section Plat.

Barton County. Sec. 13 Twp. 20 Rge. 14 (~~E~~) W (W)

Location as "NE/CNW/SW" or footage from lines NW NE SW

Lease Owner Petroleum, Inc.

Lease Name Moses "A" Well No. 1

Office Address Route 2, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed November 21 19 53

Application for plugging filed July 26 19 56

Application for plugging approved July 27 19 56

Plugging commenced August 14 19 56

Plugging completed August 21 19 56

Reason for abandonment of well or producing formation Depletion of producible zones

If a producing well is abandoned, date of last production July 14 19 56

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundage, Hoisington, Kansas
Producing formation Kansas City Depth to top 3250' Bottom 3468' Total Depth of Well 3550 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

(Plugged back to 3369')

Filled hole with crushed rock from 3369' to 3312', and placed 5 sacks cement on top of rock. Mudded up to 600' and pumped in 20 sacks mud & 90 sacks cement total; filled hole to base of well cellar with 4 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Morgan Well Plugging Service
Address 102 West 18th Street, Hutchinson, Kansas

STATE OF KANSAS COUNTY OF BARTON ss
DON SEARLE (employee of owner) or (XXXX)

DON SEARLE (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Route 2, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 27th day of August, 19 56

My commission expires July 11, 1960

Notary Public.

RECEIVED
STATE CORPORATION COMMISSION

AUG 29 1958

CONSERVATION DIVISION
Tohima, Kansas

PLUGGING
FILE SEC 13 T 20 R 14W
BOOK PAGE 84 LINE 10

Petroleum, Inc., Operator

Section 13, Twp. 20S, Rge. 11W

Garvey Drilling Company, Contractor

Location: NW NE SW

Drilling Commenced: November 2, 1953

County: Barton County, Kansas

Drilling Completed: November 12, 1953

Production: Lansing

Casing Record: 8 5/8" @ 498' w/325 sax
4 1/2" @ 3450'

R.T.D.: 3550'

Figures below indicate bottom of formation:

		<u>Tops</u>
125	Sand	
275	Sand	
380	Shale	Heebner: 3140 (-1251)
440	Sand	Brown Lime: 3240 (-1357)
500	Shale	Lansing: 3253 (-1370)
790	Shale & Red Bed	Arbuckle: 3542 (-1639)
805	Anhydrite	
1200	Shale & Shells	
1560	Shale	
1680	Shale & Shells	
1990	Lime	
2110	Lime & Shale	
2712	Shale	
2779	Lime	
3035	Lime & Shale	
3550	Lime	
3550	R.T.D.	

I hereby certify that this is a true and correct log of the above mentioned well.

PETROLEUM, INC.

By W. W. T. L.

STATE OF KANSAS)
) SS:
COUNTY OF SEDGWICK)

Subscribed to and sworn to before me, a Notary Public, in said County and State, this 18th day of November, 1953.

Charlotte M. H.
Notary Public

RECEIVED
STATE CORPORATION COMMISSION
AUG 25 1953
CONSERVATION DIVISION
Wichita, Kansas

My commission expires: October 13, 1954.

PLUGGING
FILE SEC 13 T 20 R 14W
BOOK PAGE 84 LINE 10