

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

15.009.00243.0000

orig/SCC (8/10/60)  
pc/Ks. Geol. Soc.  
(8/10/60)

WELL PLUGGING RECORD

Barton County, Sec. 3 Twp. 20 Rge. (E) 12 (W)

Location as "NE/CNW/SW" or footage from lines SW-Se-Se  
Lease Owner Herman Geo. Kaiser  
Lease Name Hood Well No. L-A  
Office Address Ellinwood, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed March 30 1959  
Application for plugging filed July 13 1960  
Application for plugging approved July 15 1960  
Plugging commenced July 22 1960  
Plugging completed July 27 1960  
Reason for abandonment of well or producing formation \_\_\_\_\_

NORTH


Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Donald Truan  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3440 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	268'	None
				5 1/2"	3429'	2564.94'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Sanded hole to 3340' - dumped 5 sks cement  
pulled pipe - pumped 15 sks Gel mud and 80  
sks cement in 8 5/8" casing.

RECEIVED  
STATE CORPORATION COMMISSION

AUG 11 1960

CONSERVATION DIVISION  
Wichita, Kansas

RECEIVED

AUG 10 1960  
HERMAN GEO. KAISER  
OIL PRODUCERS

8-11-60

Name of Plugging Contractor R & D Casing Pulling Co. License # 236  
Address Box 154 Ellinwood, Kansas

STATE OF Kansas COUNTY OF Barton, ss.  
I, W. J. Hall (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

SUBSCRIBED AND SWORN TO before me this 9th day of August, 19 60

My commission expires May 13, 1961

Notary Public.

# DRILLER'S WELL LOG

OPERATOR: **HERMAN GEO. KAISER**  
**905 Palace Building**  
**Tulsa, Oklahoma**

WELL NAME: **#1 HOOD "A"**  
 LOCATION: **SW SE SE**  
**Sec. 3-20S-12W**  
**BARTON CO, KANSAS**

CONTRACTOR: **K & E DRILLING, INC.**  
**719 UNION CENTER BLDG.**  
**WICHITA, KANSAS**

COMMENCED: **March 20th, 1959**

CASING RECORD: **8-5/8" @ 268' (250 sx)**  
**4-1/2" @ 3439' (125 sx)**

COMPLETED: **March 30th, 1959**

ELEVATION: **1804' KB**

ROTARY TOTAL DEPTH. **3440'**

PRODUCTION: **OIL**

## FORMATION RECORD

*Depths shown indicate bottom of formations encountered.*

Sand	130
Shale	230
Sand	255
Shale	268
Red Bed	656
Anhydrite	620
Shale & Shells	915
Shale	1515
Shale & Lime	1735
Lime & Shale	2220
Shale & Lime	2480
Lime & Shale	2670
Lime	2975
Shale	3085
Lime	3440
R.T.D.	3440

**RECEIVED**  
 STATE CORPORATION COMMISSION

JUL 14 1960

CONSERVATION DIVISION  
 Wichita, Kansas

## CERTIFICATION

State of KANSAS  
 County of SEDGWICK ss:

I, **Wayne L. Brinegar**, of **K & E DRILLING, INC.**, upon oath state  
 that the above and foregoing is a true and correct copy of the Driller's Log of the above named well.

*Wayne L. Brinegar*  
**Wayne L. Brinegar**

Subscribed and sworn to before me this **3rd** day of **April**, 19**59**

Notary Public  
**Patricia M. Edwards**

Witnessed and attested: **August 11th, 1962.**

