

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Barton County, Sec. 3 Twp. 20 Rge. 12 (E) (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines C S/2 SE NE

Lease Owner Simon Lebow

Lease Name Buschmann Well No. 1

Office Address 608 Oil Capital Building, Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole.

Date well completed 2/16 19 52

Application for plugging filed 2/16 19 52

Application for plugging approved 2/16 19 52

Plugging commenced 2/16 19 52

Plugging completed 2/16 19 52

Reason for abandonment of well or producing formation D. & A.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. C. D. Stough

Producing formation Depth to top Bottom Total Depth of Well 3386 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
	No Oil string of casing run.			8 2/8"	222	None.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud from 3386' to 220'. Set bridge at 220' and filled with 15 sacks cement. Filled with heavy mud to 35' and cemented with 10 sacks to bottom of cellar.

2-29-52

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Pickrell Drilling Company
Address 705 Fourth National Bank Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
C. W. Sebitts (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *[Signature]*


705 Fourth National Bank Bldg., Wichita, Kans.

(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of February, 19 52

My commission expires January 28, 1953.

[Signature]
Notary Public.



COMPANY: SIMON LEBOW ET AL
Tulsa, Oklahoma
Rotary Drilling Commenced: 2/6/52
Rotary Drilling Completed: 2/16/52

LOCATION: BUSCHMANN #1, C S/2 SE NE 3-20-12
Barton County, Kansas

CONTRACTOR: PICKRELL DRILLING COMPANY
Wichita, Kansas

CASING RECORD: 222' 8 5/8" 24# casing set at 222' in a 12 1/4" hole, cemented with 160 sacks cement.

Filled hole with heavy mud from 3386' to 220'. Set bridge at 220' and filled with 15 sacks cement. Filled with heavy mud to 35' and cemented with 10 sacks to bottom of cellar.

L O G

Surface clay & Sand	140	Circulate for samples @ 3172'.
Shale	222	" " " " 3174'.
Surface Sand & Clay	290	" " " " 3195'.
Red Bed & Sand	600	" " " " 3239'.
Anhydrite	612	" " " " 3290'.
Shale	730	" " " " 3341'.
Shale & Salt	1330	" " " " 3348'.
Shale & Lime	1940	" " " " 3351'.
Shale & Shells	2525	" " " " 3353'.
Shale	2660	" " " " 3356'.
Lime & Shale	2810	" " " " 3362'.
Lime	2866	" " " " 3368'.
Lime & Shale	2960	" " " " 3374'.
Lime	3039	" " " " 3380'.
Shale	3085	" " " " 3386'.
Lime	3386	Rotary TD Slope test at 2800' - 0° off.
		SLM @ 2800 - O.K.
		SLM @ 3386 - O.K.

The undersigned, C. W. Sebitts, Attorney-in-fact of PICKRELL DRILLING COMPANY, hereby certifies in behalf of said company, that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY
By C. W. Sebitts
Attorney-in-fact

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

FEB 29 1952
DIVISION
WICHITA, KANSAS

On this 28th day of February, 1952, before me the undersigned, a Notary Public in and for the County and State aforesaid personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of Pickrell Drilling Company to the foregoing instrument as its Attorney-in-fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

Ethe Zimmerman
Notary Public

My commission expires January 28, 1953.

PLUGGING
FILE SEC 3 T 20 R 12 W
PAGE 185 LINE 5