

RECEIVED
STATE CORPORATION COMMISSION
NOV 5 1971
CONSERVATION DIVISION
Wichita, Kansas Form CP-4


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

Barton County, Sec. 3 Twp. 20S Rge. (E) 12 (W)

Location as "NE/CNW/SW" or footage from lines NE SE NW
Lease Owner Beacon Resources Corporation
Lease Name Musenberg Well No. 1
Office Address 1000 Century Plaza, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed November 1, 19 71
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced November 1, 19 71
Plugging completed November 1, 19 71
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (Donald Truan of Russell)

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 3445 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	238'	8-5/8"	238'	None
	Casing					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy Mud from Total Depth to 480 Feet,
Plug and 40 sax cement; Mud to 220 Feet,
Plug and 25 sax cement; Mud to 40 Feet,
Plug, 1/2 sax Halls & 10 sax cement to
Base of Cellar; 3 sax cement in Rat Hole.
Job completed @ 8:00 P.M. by Dowell.


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Dowell,
Address Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, SS.
Clarence Michael of Sage Drilling Co. (employee of owner) or (owner or operator) of the above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed and that the same are true and correct. So help me God.

(Signature) Clarence Michael
500 Bitting Bldg., Wichita, Kansas
(Address)

Subscribed and Sworn to before me this 2nd day of November, 1971.
November 26, 1974.
Louise K. Whitted - Notary Public.



15.009.20631.0000

RECEIVED
STATE CORPORATION COMMISSION
NOV 5 1971
CONSERVATION DIVISION
Wichita, Kansas

DRILLERS LOG

MUSENBERG NO. 1

CASING RECORD:	OPERATOR: Beacon Resources Corp.	DESCRIPTION:
8-5/8" @ 238'	CONTRACTOR: Sage Drilling Co., Inc.	NE SE NW
w/225 sax cement	COMMENCED: October 26, 1971	Sec. 3-20S-12W
TOTAL DEPTH:	COMPLETED: November 1, 1971	Barton Co., Kansas
3445'		ELEVATION: 1810KB

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand	0	112	
Pyrite & Hard Sand	112	120	
Hard Sand	120	243	
Red Bed	243	621	
Anhydrite	621	635	
Shale	635	1245	
Shale & Lime	1245	1706	
Lime & Shale	1706	1964	
Shale & Lime	1964	2440	
Lime & Shale	2440	3090	
Lime	3090	3155	
Lime & Shale	3155	3280	
Lime	3280	3325	
Lime & Shale	3325	3388	
Lime	3388	3422	
Chert	3422	3445	D&A

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By Clarence Michael
Clarence Michael



Subscribed and sworn to before me this 4th day of November, 1971.

Louise K. Whitted
Louise K. Whitted, Notary Public

My Commission expires:
November 26, 1974.