

15.009.22598.0000

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

COUNTY Barton SEC. 3 TWP. 20 RGE. 12 N/W  
 Location as in quarters or footage from lines:  
NE SW SE


Lease Owner D & S., Inc.  
 Lease Name Doonan Well No. #1  
 Office Address Hwys. 56 & 156 Great Bend, KS 67530  
 Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_  
 Date Well Completed 1-18-82  
 Application for plugging filed 1-18-82  
 Plugging commenced 1-18-82  
 Plugging completed 1-18-82  
 Reason for abandonment of well or producing formation \_\_\_\_\_

Locate Well  
 correctly on above  
 Section Platt.

Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well J. H. Metz

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3410'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud  
 fluid was placed and the method or methods used in introducing it into the hold. If cement  
 or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
 to \_\_\_\_\_ feet for each plug set.

Bottom Plug: @ 500' w/60 sacks cement thru drill pipe  
 Middle Plug: @ 240' w/40 " " " " "  
 Top Plug: @ 40' w/1/2 sack Hulls & 10 sacks cement  
 10 sacks cement in Rat Hole

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor: Duke Drilling Co., Inc.

STATE OF Kansas COUNTY OF Barton, ss.  
Leonard Williamson (employee of owner) or (owner or operator) of the  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the  
 facts, statements, and matters herein contained and the log of the above-described well as  
 filed and that the same are true and correct. So help me God.

(Signature) Leonard Williamson  
 Box 823 Great Bend, KS 67530  
 (Address)

SUBSCRIBED AND SWORN TO before me this 20 day of January, 1982.

Deborah M. Hague  
 Notary Public.

My Commission expires: 4-11-1982

RECEIVED  
 STATE CORPORATION COMMISSION  
 JAN 21 1982  
 CONSERVATION DIVISION  
 Wichita, Kansas  
 1-21-82

5:009 22598 0000

DRILLERS' WELL LOG

DATE COMMENCED: January 13, 1982

DATE COMPLETED: January 18, 1982

D & S., Inc.  
DOONAN #1  
NE SW SE  
Sec. 3, T20S, R12W  
Barton County, Ks.

0 - 79'	Surface Soil, Shale
79 - 120'	Sand
120 - 243'	Blue Shale, Sand
243 - 594'	Shale, Shells Red Bed
594 - 617'	Anhydrite
617 - 810'	Shale
810 - 1490'	Shale & Shells
1490 - 2741'	Shale & Lime
2741 - 2982'	Lime
2982 - 2997'	Shale & Lime
2997 - 3015'	Lime
3015 - 3102'	Shale
3102 - 3119'	Lime & Shale
3119 - 3360'	Lime
3360 - 3396'	Shale, Conglomerate
3396 - 3410'	Dolomite
3410'	RTD

ELEVATION: 1806 K.B.

FORMATION DATA

Anhydrite	594'
Topeka	2741'
Heebner	2982'
Toronto	2997'
Douglas	3015'
Br. Lime	3102'
Kansas City	3119'
Base K.C.	3360'
Conglomerate	3366'
Arbuckle	3396'
RTD	3410'

Surface Pipe: Set new 20#,  
3-5/8" pipe at 242' w/200  
sacks 60/40 pozmix, 2% gel,  
3% cc.

A F F I D A V I T

STATE OF KANSAS  
COUNTY OF BARTON) ss

Leonard Williamson of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

*Leonard Williamson*

Subscribed and sworn to before me this 20 day of January, 1982.

My Comm. Expires:

4-11-1982

*Walter M. Waugh*  
Notary Public

RECEIVED  
STATE CORPORATION COMMISSION

JAN 21 1982

CONSERVATION DIVISION  
Wichita, Kansas