

15.009.04877.0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER Completed
11-15-62
LEASE NAME Hulme
WELL NUMBER "C" #6

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

990 Ft. from S Section Line
1650 Ft. from E Section Line
SEC. 9 TWP. 20 RGE. 12 (E) or (W)
COUNTY Barton
Date Well Completed 11/15/62
Plugging Commenced 12/12/95
Plugging Completed 12/13/95

LEASE OPERATOR Pauline Byars Oil Production
ADDRESS Box 698, Great Bend, Ks. 67530
PHONE # 816-792-2506 OPERATORS LICENSE NO. 6596
Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10/13/95 (date)
by Mr. Hubert Deines and witnessed by Mr. Ken Kuhn (KCC District Agent's Name).

Is ACO-1 filed? N. A. If not, is well log attached? Filed with CP-1

Producing Formation Lansing-K. C. Depth to Top 3,161' Bottom 3,444' T.D. 3,456'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	201'	None
	<u>2-7-96</u>			4 1/2"	3,443'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Perforated shots @ 1,500-01', 700-701' & 350-351'. Ran tubing to 2,077'. Halliburton pumped 100% hulls blended in 50 sx 60/40 pozmix cement with 10% gel thru tubing. Pulled tubing to 1,447' and pumped 50 sx cement. Pulled tubing to 724' and pumped 100 sx cement circulated to surface. Pulled tubing, filled 4 1/2" casing with cement and pumped 60 sx cement in the annulus at 225 psi. Job finished at 12:00 noon.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Pauline Byars Oil Production

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (Employee of Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold
James W. Rockhold
(Address) Box 698, Gt. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 29th day of January, 19 96

Jona M. Leatherman
Notary Public

My Commission Expires: 