


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Barton County, Sec. 13 Twp. 22 Rge. 14 (E) (W)  
Location as "NE/CNW/SW" or footage from lines \_\_\_\_\_  
Lease Owner Lee Phillips Oil Co.  
Lease Name Dahm Well No. 1  
Office Address Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed June 28 19 19 54  
Application for plugging filed June 19 19 54  
Application for plugging approved June 19 19 54  
Plugging commenced June 19 19 54  
Plugging completed June 19 19 54

Reason for abandonment of well or producing formation \_\_\_\_\_  
If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. H. Horner  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3420 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	250	8 5/8	6-10-54	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Pushed 1/3 sack hulls and Halliburton plug to 240'. Place 20 sacks cement through drill pipe onto plug. Filled surface pipe to 30' with heavy mud. Placed 1/3 sack of hulls and Halliburton plug to 30'. Placed 10 sack cement through drill pipe onto plug. Cement in pipe to cellar level.

RECEIVED  
CORPORATION COMMISSION

JUN 27 1954

6-29-54

CONSERVATION DIVISION  
WICHITA, KANSAS

Name of Plugging Contractor Clark Knight Drilling Co.  
Address Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
L. C. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me, God.

(Signature) L. C. Knight  
Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 25<sup>th</sup> day of June, 1954

Chatter J. Volk  
Notary Public.

My commission expires Sept. 15, 1956

PLUGGING  
FILE SEC 9 T 20 R 12W  
BOOK PAGE 43 LINE 10

## WELL LOG

Lee Phillips Oil Co.

Lease: Dahm  
Well No: 1Sec. 13-22-14  
Barton County, KansasTotal Depth: 3420 R.B.  
Comm: 6-10-54 Comp: 6-20-54  
Contractor: Clark Knight Drilling Co.  
Rotary: 0-3420Elevation: 1820 D.F.  
Production: D. & A.Casing Record: 8 5/8" set @ 250' cemented w/200 sack bulk  
cement, circulated.

Figures indicated bottom of formations:

Sand & Clay	115
Shale & Shells	145
Shale & Iron	160
Shale & Shells	625
Anhydrite	655
Shale & Shells	1005
Salt & Shells	1050
Shale & Shells	1460
Lime & Shale	2940
Lime	3090
Lime & Shale	3143
Lime	3261
Lime & Shale	3290
Lime	3339
Lime & Shale	3413
Lime	3420

We hereby certify this to be a correct and accurate log of the  
above described well as shown on the daily drilling reports.

Clark Knight Drilling Co.

By *Clark Knight*Subscribed and sworn to before me this 25<sup>th</sup> day June, 1954

My Commission Expires

Sept. 15, 1956*Walter J. Volk*  
Notary PublicRECEIVED  
STATE CORPORATION COMMISSION

JUN 29 1954

CONSERVATION DIVISION  
WICHITA