


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Barton County. Sec. 9 Twp. 20 Rge. 12W (W)  
Location as "NE/CNW/SW" or footage from lines SW NE SW  
Lease Owner Charles Hulme Drilling  
Lease Name Hulme "C" Well No. 4  
Office Address Box 36 Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed November 30, 19 61  
Application for plugging filed \_\_\_\_\_ 19 \_\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19 \_\_\_\_\_  
Plugging commenced April 18, 19 62  
Plugging completed April 18, 19 62  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Donald Truan  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3470' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	215'	
				4 1/2"	3450'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Sanded hole back to 3400' & dumped 4 sacks cement with dump bailer. Pulled pipe. Squeezed well with 10 sacks mud & 80 sacks cement with Halliburton Cementing Company's pump truck, cementing from 250' to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 23 1967

CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor Forbes Casing Pulling Company  
Address Box 221 Great Bend, Kansas

STATE OF KANSAS COUNTY OF BARTON  
C. E. BYARS (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) C. E. Byars  
Box 836 Great Bend, KS.  
(Address)

SUBSCRIBED AND SWORN to before me this 22<sup>ND</sup> day of MARCH, 19 67

David H. Schuer  
Notary Public.

My commission expires 9-29-69

COPY

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, KansasCompany. CHAS. HULME DRILLING  
Farm. Hulme "C" No. 4SEC. 9 T. 20 R. 12W  
SW NE SWTotal Depth. 3474'  
Comm. 11-15-61 Comp. 11-30-61  
Shot or Treated.  
Contractor.  
Issued. 2-17-62County Barton  
KANSASCASING:  
8 5/8" 215' cem w/415 sx.  
4 1/2" 3450' cem w/100 sx.

Elevation. 1822' DE

Production. Dry

Figures indicate Bottom of Formations.

sand, blue clay	215
shale	300
red bed	635
Anhydrite	660
shale & shells	860
shale	1220
lime & shale	2235
shale	2405
lime & shale	2560
shale	2639
lime & shale	2932
lime	3450 RTD
lime	3474
Total Depth	

## TOPS:

Anhydrite	635
Heebner	3019
Brown Limestone	3139
Kansas City	3154
Conglomerate	3389
Arbuckle	3400

DST #1 T.D. 3186', packer set @ 3156',  
op 20 mins, slight blow for 19 mins,  
rec. 10' slightly oil specked mud.  
BHP 40#.

DST #2 packer set at 3410', T.D. 3430',  
op 30 mins, slight blow for 8 mins,  
rec. 10' mud. No show of oil. No BHP.

DST #3 T.D. 3450', packer set at 3430',  
op 20 mins, slight blow for 8 mins.  
Rec. 10' mud. Slightly oil specked  
with BHP of 850#.

RECEIVED  
STATE CORPORATION COMMISSION

JUL 16 1964

CONSERVATION DIVISION  
Wichita, Kansas