

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Barton County, Sec. 9 Twp. 20 Rge. 12 (E) (W)

Location as "NE/CNW/SW" or footage from lines NW SE SE

Lease Owner Chas Hulme Drilling Contractor

Lease Name Hulme Well No. C-1

Office Address P. O. Box 836 Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) _____

Date well completed _____ 19__

Application for plugging filed 11-6-63 19__

Application for plugging approved 11-7-63 19__

Plugging commenced 11-7-63 19__

Plugging completed 11-19-63 19__

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production _____ 19__

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Thuan

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3170 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	285	None
				4 1/2	None	1638

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Moved in. Cleaned out cellar. Sanded to 3050'. Dumped 3 sacks of cement. Working pipe.

Loaded hole with water. Working pipe. Shot at 2850' - 2720'.

Circulating. Spotted 40 bbls. of oil.

Working pipe. Shot at 2000' - 1900' - 1800' - 1700' and 1620'.

Pulling pipe.

Squeezed well with 10 sacks of mud and 80 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION
NOV 26 1963
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.

Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas COUNTY OF Barton, ss.

J. O. Forbes (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes

P. O. Box 221 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 22 day of November, 19 63

My commission expires May 27, 1964

Notary Public.

Chas. Hulme Drilling Contractor
 P. O. Box 836
Great Bend Kansas

Hulme C-1

NW SE SE 9-20-12

Barton County, Kansas

0 - 130	Sand	Elevation	1839' D. F.
130 - 285	Sand & blue shale		1842' R. B.
285 - 645	Red bed & shells	Anhydrite	645'
645 - 665	Anhydrite	Hebner	3025' -1183'
665 - 1180	Shale & shells	Brown Lime	3143' -1301'
1180 - 1450	Shale	Kansas City	3156' -1314'
1450 - 1775	Shale & lime		
1775 - 1905	Lime		
1905 - 2895	Shale & lime		
2895 - 3060	Lime		
3060 - 3150	Lime & shale		
3150 - 3470	Lime		
3470	Rotary T. D.		

RECEIVED
 STATE CORPORATION COMMISSION

NOV 8 1963

CONSERVATION DIVISION
 Wichita, Kansas

8 5/8" set at 285' and cemented with 300 sacks cement.

Drill Stem Test # 1

Packer set at 3422'. TD 3435'. Open 1 hour. Slight blow for 12 minutes. Recovered 20' slightly oil cut mud with 609 lbs. BHP.

Drill Stem Test # 2

Packer set at 3435'. TD 3450'. Open 1 hour. Slight blow for full hour. Recovered 150' heavily oil cut mud. (Trace of water questionable) BHP 812 lbs.

4 1/2" OD casing set at 3470' and cemented with 100 sacks cement.

STATE OF KANSAS
 COUNTY OF BARTON ss

Virgil E. Belford, Jr., employee of Chas. Hulme Drilling Contractor, being first duly sworn on oath says: That I have knowledge of the facts, statement, and matters herein contained and the log of the above described well as filed and that the same are true and correct.


 Virgil E. Belford, Jr.

Subscribed and sworn before me this 29th day of April 1961.


 Notary Public Barton County

My Commission Expires: 12-3-63