


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Barton County, Sec. 9 Twp. 20S Rge. 12W(E) (W)
Location as "NE/CNW/SW" or footage from lines. C S/2 SE NE
Lease Owner Neven H. Veail
Lease Name Brining Well No. 1
Office Address 1401 McKinley Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed June 30 1967
Application for plugging filed June 30 1967
Application for plugging approved June 30 1967
Plugging commenced 11:30 PM June 30, 1967
Plugging completed 1:30 AM July 1, 1967
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production. 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Don Truman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud to 300 feet
Plug 20 sacks of cement,
Heavy mud to 180 feet
Plug 1/4 sack of hulls, 20 sacks of cement
Heavy mud to 40 feet
Plug 1/2 sack of hulls, 10sacks of cement
Plugged with Globe Cementing, Inc. Truck

RECEIVED
STATE CORPORATION COMMISSION
JUL 13 1967
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Peel Brothers, Inc.
Address Box 359, Holdington, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Neven H. Veail
1401 McKinley; Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of July, 1967

My commission expires February 15, 1968 Notary Public.

DRILLER'S LOG

Well Owner: Neven H. Veail
Farm Name: Brining No. 1
Date Started: 6-24-67
Date Completed: 7-1-67
Total Depth: 3462

C/S $\frac{1}{2}$ NE SE
Section 9-20S-12W
Barton County, Kansas

Casing: 8-5/8" set at 184' cemented

Contractor: Peel Brothers, Inc.

Bottoms of formations are as follows:


Sand and Clay	0 - 70
Sand and Iron	117
Shale	188
Red Bed and Shells	615
Anhydrite	630
Shale and Shells	1425
Shale and Lime	2450
Lime and Shale	3180
Lime	3462
Total Depth	3462

This is to certify that the above information is to the best of our knowledge true and correct.

PEEL BROTHERS, INC.

Wendell C. Peel
Wendell C. Peel
President

RECEIVED
STATE CORPORATION COMMISSION
JUL 13 1967



SUBSCRIBED AND SWORN to before me this 10th day of July, 1967.

Ethel S. Williamson
Ethel S. Williamson
Notary Public

CONSERVATION DIVISION
MICHIGAN, KANSAS

My Commission expires 6-21-70