

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 009 - 20470 - 0000 (of this well)

Operator's Full Name National Oil Co.
Complete Address 200 W. Douglas, Suite 550, Wichita, Kansas 67202
Lease Name Brining Well No. 2
Location SE NW NE Sec. 9 Twp. 20 Rge. 12 ~~XX~~ (W) X
County Baron Total Depth 3414'
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Kelso Casing Pulling
Address Box 176 Chase, Kansas 67524 License No. 683
Operation Completed: Hour 11:00 AM Day 12 Month 9 Year 1978
The above well was plugged as follows:

Sanded back to 3375' and 5 sx cement with dump bailer.

Squeezed thru 8 5/8" surface casing with 4 sx hulls, ~~17/16~~,
25 sx mud gel, plug, and 100 sx cement.

Max. Pres. 500#. Shut in pres. 100#.

Recovered 2406' of 5 1/2" casing.

3380' of 5 1/2" casing cemented with 100 sx cement.

210' of 8 5/8" surface casing cement circ.

RECEIVED
STATE CORPORATION COMMISSION

SEP 14 1978

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9-14-78

INV. NO. 8082.W

Signed: Duane Rankin
Well Plugging Supervisor