

KANSAS

JP

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 5 1967
CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Neven H. Veail

Complete Address: 1401 McKinley, Great Bend, Kansas 67530

Lease Name Brining Well No. # 1

Location C S/2 SE NE Sec. 9 Twp. 20 Rge. 12 (E) (W) W

County Barton Total Depth 3462

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Peel Brothers, Inc.

Address: Box 359, Hoisington, Kansas License No. _____

Operation Completed: Hour 2 AM Day 1 Month 7 Year 1967

The Above well was plugged as follows:

8 5/8" 183' Cwc.
Circulated hole with heavy mud to 300', set plug, & displaced 20 sax cement thru drill
pipe. Mud to 180', set plug with 1/4 sax hulls, & displaced 20 sax cement thru drill
pipe. Mud to 40', 1/2 sax hulls, plug, & displaced 10 sax cement with Globe Cementing
Company's pump truck, cementing to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Don Arush
Well Plugging Supervisor

DATE 7/5/67

INV. NO. 5518-W