

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 1-39LOCATION NW-NW-SESEC. 5 TWP. 20 RGE. 12 WDry Hole Abandoned Oil Well ✓ Abandoned Gas Well

I have this date completed supervision of plugging of:

Well No. 1 Lease Lanterman "A"Operator Hilton Drilling Co. Inc. Address Great Bend, Kansas.Field County BartonTotal Depth 3438 Feet.Plugging Contractor Joe Pipe Pulling Co.Plugging Contractor's License No. 2Address Great Bend, Kansas.

(Describe briefly the manner in which the well was plugged)

Surface pipe 8 7/8" @ 120' c.w.c. 5 1/2" Oil string
Set 3437' w/ 150 sv Cem. P.B. 3245 top perf.
3218' Sanded hole to 3210' dumped 5 sv Cem.
Shot off and pulled 5 1/2" casing. Pumped
15 sv fresh fell mud, Plug and 85 sv Cem.
Filling hole and surface pipe from
855' to base of cellar with Cem.
Hlobe Cem. Co.

Warren H. Garner
District Conservation Agent

Date Sept 29, 1955

RECEIVED
STATE CORPORATION COMMISSION

OCT 3 1955

CONSERVATION DIVISION
Wichita, Kansas

PLUGGINGFILE NO. 4120-224BOOK PAGE 1 LINE 39