

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
 Conservation Division
 211 North Broadway
 Wichita, Kansas

FILE NO. 148-29LOCATION SW-SW-NESEC. 5 TWP. 20 RGE. 12W

Dry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Lanterman "A"Operator C. E. Ash et al Address 309 Petr. Bldg. Wichita, Kans.Field _____ County BartonTotal Depth 3454 Feet.Plugging Contractor R. S. Pipe Pulling Co.Plugging Contractor's License No. 1Address Ellinwood, Kansas

(Describe briefly the manner in which the well was plugged)

Surface pipe 8" @ 175' cwc 5 1/2" @ 3438' w/ 50 cc
 Cem. P.B. 3411 top Ref. 3403' Sanded hole to
 3395' dumped 5 cc Cem. Shot off and pulled
 5 1/2" casing. Filled hole with heavy mud
 to 175' set rock bridge and dumped 20 cc
 Cem. mud to 35' rock bridge and 10 cc
 Cem. to base of collar

Warren H. Harner
 District Conservation Agent

Date Oct. 10, 1955

RECEIVED
 STATE CORPORATION COMMISSION

OCT 15 1955

CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
 FILE SEC 5 TWP. 20 R. 12W
 BOOK PAGE 48 LINE 29