

15.009.02041-0000

R

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Joe Brougher Oil Company

Complete Address 5513 Apache, Great Bend, Kansas 67530

Lease Name Murphy Well No. # 5

Location SW NE NW Sec. 29 Twp. 20 Rge. 13 (E) (W)W

County Barton Total Depth 3439

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Russ Casing Pulling, Inc.

Address Box 1082, Great Bend, Kansas License No. 623

Operation Completed: Hour 11:30 A.M. Day 18 Month 8 Year 1969

The above well was plugged as follows:

8 5/8" Cwc. @ 132', 5 1/2 " 3438' Cwc. 60 Sax.

Sanded hole back to 3130' & dumped 5 sax cement with dump bailer.

Pulled pipe, Squeezed well with 5 sax hulls, 20 sax mud, & 100 sax cement with

Allied Cementing Company's pump truck, cementing to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8-21-69
344-W

INV. NO. 344-W
355-W

Signed: [Signature]
Well Plugging Supervisor