

## TO:

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-205-21100-00-00Spot: NENESESESec/Twnshp/Rge: 2-29S-14E1051 feet from S Section Line,138 feet from E Section LineLease Name: K LOETHERWell #: 8County: WILSONTotal Vertical Depth: 1130 feetOperator License No.: 34697Op Name: WILSON COUNTY HOLDINGS LLCAddress: 1135 N. 15TH ST.  
FREDONIA, KS 66736

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	2.375	1120		115 SX
SURF	5	40		12 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 05/30/2017 12:00 PMPlug Co. License No.: 33749Plug Co. Name: KEPLEY WELL SERVICE, LLCProposal Rcvd. from: FORREST SUTHERLAND

Company:

Phone: (620) 325-4344

Proposed Plugging Method: Run one inch pipe to TD of whole and pump 15ppg cement to surface. Trip pipe out and top well off with cement than cut well off below plow depth.

Plugging Proposal Received By: ALAN DUNNINGWitnessType: NONEDate/Time Plugging Completed: 05/30/2017 12:00 PMKCC Agent: ALAN DUNNING

## Actual Plugging Report:

Perfs:

The wellhead was directly connected to and circulation established by pumping 6 bbls of water. The well was then pumped full of cement that contained cottonseed hulls by squeezing. The well was shut in with 700 psi. A total of 84 sacks of portland cement were used to plug well.

RECEIVED  
KCC DIST #3

FEB 21 2018

CHANUTE, KS

AD

INVOICED

APR 18 2018

Remarks:

Plugged through: CSGDistrict: 03

Signed



(TECHNICIAN)