

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-007-20717-00-02  
Spot: SESESE Sec/Twnshp/Rge: 1-33S-11W  
330 feet from S Section Line, 330 feet from E Section Line  
Lease Name: DAVIS Well #: 1OWWO  
County: BARBER Total Vertical Depth: 5105 feet

Operator License No.: 33168  
Op Name: WOOLSEY OPERATING COMPANY, LL  
Address: 125 N MARKET STE 1000  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4610		WITH 2 SX CMT
PROD	4.5	5074	2440	WITH 210 SX CMT
SURF	8.625	273		WITH 250 SX CMT

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/09/2018 2:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Revd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: CIBP @ 4610' WITH 2 SX CMT. PLUG AT 610' WITH 10 SX GEL & 50 SX CMT. PLUG AT 310' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: NONE  
Date/Time Plugging Completed: 02/09/2018 3:30 PM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

Perfs:

SET CIBP @ 4610' WITH 2 SX CMT. 1ST PLUG AT 610' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 310' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 30 SX CMT. CMT CIRCULATED.

Top	Bot	Thru	Comments
4660	4675		MISSISSIPPI

INVOICED

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

APR 18 2018

Plugged through: CSG

District: 01

Signed \_\_\_\_\_

*[Signature]*  
51A (TECHNICIAN)

RECEIVED  
FEB 12 2018  
KCC DODGE CITY