

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-21022-00-00
Spot: SESENW Sec/Twnshp/Rge: 7-33S-12W
2970 feet from S Section Line, 2970 feet from E Section Line
Lease Name: HOSPITAL Well #: 1
County: BARBER Total Vertical Depth: 4575 feet

Operator License No.: 33168
Op Name: WOOLSEY OPERATING COMPANY, LL
Address: 125 N MARKET STE 1000
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4450		WITH 2 SX CMT
PROD	4.5	4554	1210	WITH 150 SX CMT
SURF	8.625	225		WITH 200 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/07/2018 2:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: CIBP @ 4450' WITH 2 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 270' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: NONE
Date/Time Plugging Completed: 02/07/2018 5:30 PM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

Perfs:

CIBP @ 4450' WITH 2 SX CMT. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT.
2ND PLUG AT 270' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 25 SX CMT.

Top	Bot	Thru	Comments
4499	4515		

INVOICED
APR 18 2018

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed _____
SR

(TECHNICIAN)

RECEIVED
FEB - 9 2018
KCC DODGE CITY *MR*