

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-007-22582-00-00  
Spot: SESWNENE Sec/Twnshp/Rge: 8-34S-13W  
1160 feet from N Section Line, 830 feet from E Section Line  
Lease Name: JIM DONOVAN Well #: A-1  
County: BARBER Total Vertical Depth: 5550 feet

Operator License No.: 33168  
Op Name: WOOLSEY OPERATING COMPANY, LL  
Address: 125 N MARKET STE 1000  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4850		WITH 2 SX CMT
PROD	4.5	5167	1420	WITH 100 SX CMT
SURF	10.75	348		WITH 300 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/05/2018 12:15 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: CIBP @ 4850' WITH 2 SX CMT. PLUG AT 820' WITH 12 SX GEL & 50 SX CMT. PLUG AT 370' WITH 80 SX CMT. PLUG AT 40' WITH 30 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 02/05/2018 3:45 PM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

CIBP @ 4850' WITH 2 SX CMT. 1ST PLUG AT 810' WITH 12 SX GEL & 50 SX CMT. PIPE STUCK. SHOOT OFF AT 710'. STILL STUCK. SHOT AT 410'. PULL 1 JOINT PIPE. 2ND PLUG AT 370' WITH 80 SX CMT. 3RD PLUG AT 40' WITH 35 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4985	4995		
4909	4919		
4882	4892		

INVOICED

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

APR 18 2018

Plugged through: CSG

District: 01

Signed \_\_\_\_\_

(TECHNICIAN)

RECEIVED  
FEB - 9 2018  
KCC DODGE CITY