

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-097-21836-00-00  
Spot: NWSEWSW Sec/Twnshp/Rge: 20-28S-19W  
470 feet from S Section Line, 700 feet from W Section Line  
Lease Name: KILGORE Well #: 1  
County: KIOWA Total Vertical Depth: 5100 feet

Operator License No.: 33168  
Op Name: WOOLSEY OPERATING COMPANY, LL  
Address: 125 N MARKET STE 1000  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
11	8.625	897		WITH 125 SX CMT
SURF	10.75	353		WITH 315 SX CMT

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/12/2018 11:30 AM  
Plug Co. License No.: 34484 Plug Co. Name: FOSSIL DRILLING, INC.  
Proposal Revd. from: RICK BARRINGER Company: FOSSIL DRILLING, INC. Phone: (620) 672-5625

Proposed Plugging Method: 1ST PLUG AT 1260' WITH 50 SX CMT. 2ND PLUG AT 900' WITH 50 SX CMT. 3RD PLUG AT 350' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: NONE  
Date/Time Plugging Completed: 02/12/2018 2:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SURFACE PIPE DID NOT CIRCULATE. 1" 10 3/4" FROM 100' TO SURFACE WITH 125 SX CMT. 1ST PLUG AT 1260' WITH 50 SX CMT. 2ND PLUG AT 900' WITH 50 SX CMT. 3RD PLUG AT 350' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY BASIC.

Plugged through: DP

District: 01

Signed Stephen J. Pfeifer  
(TECHNICIAN)

RECEIVED  
FEB 26 2018  
KCC DODGE CITY

INVOICED  
APR 18 2018