

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-155-21625-00-00  
Spot: NWNWNESE Sec/Twnshp/Rge: 7-22S-7W  
2355 feet from S Section Line, 1100 feet from E Section Line  
Lease Name: SIEGRIST 2207 Well #: 7-2  
County: RENO Total Vertical Depth: 4016 feet

Operator License No.: 35053  
Op Name: TAPSTONE ENERGY, LLC  
Address: PO BOX 1608  
OKLAHOMA CITY, OK 73101

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3954		
COND	18	60		42 sx cement
	11 7	4016		382 SX CEMENT
PROD	7	4016		382 SX
SURF	9,625	376		270 SX
	T1 4.5	3939		

Well Type: SWD UIC Docket No: D31545.0 Date/Time to Plug: 11/14/2017 12:00 AM  
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS  
Proposal Rcvd. from: RANDY SUMMERS Company: Phone: (620) 896-7200

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL  
Date/Time Plugging Completed: 11/15/2017 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

Perfs:

TOOH LAYING DOWN 93 JOINTS 4 1/2" TUBING AND PACKER. LOADED HOLE WITH GELLED WATER. SET CIBP AT 3965'. DUMP BAILED 7 SACKS CEMENT ON PLUG. YELLOW JACKET WL RAN CEMENT BOND LOG TOC @ 0'. TIH TO 1100'. SPOT 50 SXS CEMENT. POOH TO 600' AND CIRCUALTE 120 SX CEMENT TO SURFACE. CUT OFF WELL HEAD AND WELD ON ID PLATE.

INVOICED

APR 18 2018

Remarks: BASIC ENERGY WAS CEMENTERS ON THIS JOB - TICKET #16135 - DENIED TA - NO LEASE

Plugged through: TBG

District: 02

Signed

*B. J. Hope*

(TECHNICIAN)