

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-205-21640-00-01
Spot: N2S2SESE Sec/Twnshp/Rge: 2-29S-14E
495 feet from S Section Line, 660 feet from E Section Line
Lease Name: LOETHER Well #: 11
County: WILSON Total Vertical Depth: 1156 feet

Operator License No.: 34697
Op Name: WILSON COUNTY HOLDINGS LLC
Address: 1135 N. 15TH ST.
FREDONIA, KS 66736

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD | 2.375 | 1130 | | 103 SX |
| SURF | 5 | 40 | | 13 SX |
| SURF | | 60 | | |

Well Type: EOR UIC Docket No: E21114.1 Date/Time to Plug: 05/30/2017 12:00 PM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: FORREST SUTHERLAND Company: WILSON COUNTY HOLDINGS Phone: (620) 325-4344

Proposed Plug well by using the squeeze method.
Plugging Method:

Plugging Proposal Received By: ALAN DUNNING Witness Type: NONE
Date/Time Plugging Completed: 05/30/2017 12:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

Perfs:

The wellhead was connected to directly and circulation established by pumping 5 bbls of water. The well was then pumped full of cement by squeezing. The well was shut in with 700 psi. A total of 42 sacks of portland cement that contained cottonseed hulls were used to plug well.

RECEIVED
KCC DIST # 3
FEB 21 2018
CHANUTE, KS

AD

INVOICED
APR 18 2018

Remarks:

Plugged through: CSG

District: 03

Signed Alan M. Dunning
(TECHNICIAN)