

4-060374

12-23

15.009.02035.0000

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15- - 12-28-62

NE SE NE /4 SEC. 29, 20 S, 13 W  
3630 feet from S section line  
330 feet from E section line

Operator license# 6883 Lease Engleman well # 2

Operator: Robinowitz Oil Company County Barton 116.12

Address: 7130 S. Lewis Well total depth 3573 feet  
Tulsa, OK 74136 Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 296 feet

Aband. oil well X, Gas well     , Input well     , SWD     , D & A     

Plugging contractor: Kelso Casing Pullers, Inc. License# 6050

Address: P.O. Box 347 - Chase, Kansas 67524

Company to plug at: Hour: 8:30A.M. Day: 23 Month: December Year: 92

Plugging proposal received from: Mike Kelso

Company: Kelso Casing Pullers, Inc. Phone: 316-938-2943

Were: Order 275 sxs. 60/40 pozmix - 10% gel. and hulls.  
Plug thru casing.

Plugging Proposal Received by: Herb Deines  
Plugging operations attended by agent? All[ X ], Part[      ], None[      ]

Completed: Hour: 11:45A.M. Day: 23 , Month: December , Year: 92

Actual plugging report: 8 5/8" to 296'. 5 1/2" to 3573'. Shot one time  
and pulled 2600' of casing. Sanded back to 50' above open hole and  
spotted 5 sxs. cement. Pulled casing to 1200' and loaded casing with  
110 sxs. cement and 200# hulls. Pulled casing to 700' and pumped 50  
sxs. cement. Pulled casing to 300' and circulated cement to surface with  
80 sxs. cement. Pulled casing and topped with 35 sxs. cement.

Remarks: Halliburton Cementing.

Condition of casing(in hole): GOOD X BAD      Any plug: YES X NO       
Bottom plug(in place): YES X , CALC      , NO      Dakota plug: YES X , NO       
Plugged through TUBING      , CASING X . Elevation: 1894 GL     

I did [ X ] / did not [      ] observe the plugging.

*Handwritten signature*  
STATE CORPORATION COMMISSION  
WICHITA, KANSAS  
5 1993

(agent)

Form CP-2/3

**INVOICED**

DATE 1-8-93

INV. NO. 37161