

4-010386

12-15

API Number: 15-009-23,831-0000

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

N2 NW SW /4 SEC. 29, 20 S, 13 W
2310 feet from S section line
4620 feet from E section line

Operator license# 30517

Lease: Weathers Well# C-1

Operator: Turnco

County: Barton 112,29

Address: Rt. 1 - Box 1295
Great Bend, Kansas 67530

Well total depth 3455 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 366 feet

Aband. oil well Gas well _____, Input well _____, SWD _____, D & A _____

Plugging contractor: Mike's Testing and Salvage License# -

Address: _____

Company to plug at: Hour: 9:00 A.M. Day: 15 Month: December Year: 1998

Plugging proposal received from: Mike Kelso

Company: Mike's Testing and Salvage Phone: -

Were: Same as below.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All , Part , None]

Completed: Hour: 12:30 P.M., Day: 15, Month: December, Year: 1998

Actual plugging report: Sanded to 3280' and dumped 5 sxs cement. Shot off casing at 1800'. Pulled to 1600' and pumped 110 sxs 60/40 pozmix - 10% gel cement with 300# hulls. Pulled to 800' and pumped 40 sxs cement with 100# hulls. Pulled to 250' and circulated with 50 sxs cement. Pulled casing. Topped off with 10 sxs.

Remarks: _____

Condition of casing(in hole): GOOD BAD _____ Anhy.plug: YES _____ X NO _____
Bottom plug(in place): YES _____, CALC _____, NO _____ Dakota plug: YES _____ X NO _____
Plugged through TUBING _____, CASING _____ Elevation: _____ GL

I did / did not observe the plugging. Cas Monie
(agent)

100

RECEIVED
NOV 13 1998
1555
13 40
Form CP-2/3

12-21-98

DEC 30 1998

60497