

12-30
4- 062562

232
R

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-009-22,562.0000

NE /4 SEC. 08, 20 S, 12 W
4260 feet from S section line
1800 feet from E section line

Operator license# 4707 Lease Schartz well # 8-2

Operator: Carl Boxberger Oil, Inc. County Barton

Address: P.O. Box 1604 Well total depth 3537 feet 114.95
Great Bend, Kansas 67530 Conductor Pipe: 0 inch @ 0 feet
316-793-6032 Surface pipe 8 5/8 Inch @ 296 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Kelso Casing Pulling, Inc. License# 6050

Address: Box 347, Chase, Kansas 67524

Company to plug at: Hour: 1:00P.M. Day: 30 Month: December Year: 91

Plugging proposal received from: Mike Kelso

Company: Kelso Casing Pulling, Inc. Phone: 316-938-2943

Were: Order 250 sks. of 60/40 posmix - 8% gel. - 5 sks. hulls. **RECEIVED**

KANSAS CORPORATION COMMISSION

JAN 6 1992

CONSERVATION DIVISION
WICHITA, KS

Plugging Proposal Received by: Gilbert G. Scheck

Plugging operations attended by agent? All , Part , None]

Completed: Hour: 3:00P.M., Day: 30, Month: December, Year: 91

Actual plugging report: 8 5/8" @ 296' w/200 sks. 5 1/2" @ 3536' w/150
sks. Top perf. @ 3428'. Plugged bottom with sand and 5 sks. cement to
3375'. Shot pipe 3 times and recovered 2330'. Pump in 5 1/2" casing
and circulated cement to surface from 700'. Pulled all casing and
hooked on to 8 5/8" and squeezed to 300 P.S.I.
Max. pressure on 5 1/2" - 500 P.S.I. Shut in @ 400 P.S.I.
Max. pressure on backside - 300 P.S.I. Shut in @ 200 P.S.I.
Total sacks 250 cement.

Remarks:

Condition of casing(in hole): GOOD BAD Anhy.plug: YES 725' NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: 1730' GL

I did / did not observe the plugging. Gilbert G. Scheck

DATE 1-9-92

INV. NO. 34282

(agent)

Form CP-2/3