

Kansas Corporation Commission
District Plugging Report

API Well Number: 15-037-01816-00-00
 Spot: E/2OESE Sec 2 Twp 29 S Rng 21 E / W
1835 Feet from N / S Line of Section
886 Feet from E / W Line of Section
 GPS: Lat: 37.548860 Long: 95.073520 Date: 11/13/17
 Lease Name: BRADSHAW Well #: TOM.01
 County: CRAWFORD Total Vertical Depth: 210 feet

Operator License No: 101
 Op Name: KANSAS CORPORATION COMMISSION
 Address 1: 226 N MAIN STE 220
 Address 2:
 City: WICHITA
 State: KS Zip Code: 67202

String	Size	Depth	Pulled	Comments
<u>SURF - Casing</u>	<u>7.000</u>			
<u>T1 - Tubing 1</u>	<u>2.000</u>			<u>PVC</u>
<u>T2 - Tubing 2</u>	<u>0.500</u>			<u>PVC</u>

Well Type: GAS - Natural Gas - Production UIC Docket No.: _____ Date/Time to Plug: 1/30/18 /
 Plug Co License No.: 33749 Plug Co. Name: KWS
 Proposal Rcvd from: MIKE KEPLEY Company Name: KWS Phone: 620-431-9212

Proposed Plugging Report: **CLEAN OUT WELLS TO BOTTOM. PUMP FULL OF PORTLAND CEMENT, INSIDE AND OUTSIDE OF CASING. IF CEMENT IS PRESENT IN THE ANNULUS, CASING SHOULD BE PERFORATED IN AT LEAST 2 INTERVALS, UNLESS WELL IS DOCUMENTED AS ALT. 2 COMPLETION.**

Plugging Proposal Received By: TONY ANDERSON Witness Type: COMP - Complete 100%
 Date/Time Plugging Completed: 1/30/18 / _____ KCC Agent: TONY ANDERSON

Actual Plugging Report:	Perfs:	Top	Bottom	Thru
MOVE TO LOCATION AND HAD ROCK HAULED IN TO GET TO THE WELL. PULLED 1/2" PVC LOOSE FROM SEAT NIPPLE. RAN INSIDE AND OUTSIDE OF THE 2". PUMPED 91 SACKS OF CEMENT. WELL WAS STILL VENTING. CAME BACK THE NEXT WEEK TO FINISH. RAN BACK IN TO SEAT NIPPLE, STUCK 1" IN IT AND PUMPED CEMENT. PULLED 1" AND PUT VALVE ON TO SQUEEZE. AN ADDITIONAL 65 SACKS OF CEMENT WERE USED. THE LOCATION WAS RESTORED.				

Remarks: CONTRACT#38595;CONTROL#20180015-001;NAD 83;GPS BY TONY

Plugged Thru: TBG - Tubing Plugged Due to Compliance Issue: Yes No

District: 03 **KCC WICHITA** Tony Anderson (Technician)
APR 05 2018 Form: District Plugging Report -
RECEIVED