

Kansas Corporation Commission

District Plugging Report

API Well Number: 15-059-20964-00-00
 Spot: NENENE Sec 21 Twp 17 S Rng 21 ☒ E / ☐ W
5165 Feet from ☐ N / ☒ S Line of Section
162 Feet from ☒ E / ☐ W Line of Section
 GPS: Lat: 38.564140 Long: 95.084420 Date: 12/19/17
 Lease Name: Caylor C Well #: 01 (Caycol)
 County: Franklin Total Vertical Depth: 500 feet

Operator License No: <u>101</u>	String	Size	Depth	Pulled	Comments
Op Name: <u>State of Kansas</u>	<u>SURF - Casing</u>	<u>6.000</u>	<u>20</u>	<u>0</u>	<u>EST</u>
Address 1: <u>266 N. Main St., Ste 220</u>	<u>PROD - Casing</u>	<u>2.000</u>	<u>500</u>	<u>0</u>	
Address 2: _____					
City: <u>WICHITA</u>					
State: <u>KS</u> Zip Code: <u>67202</u> - <u>1513</u>					

Well Type: OG - Oil & Gas (oil) UIC Docket No.: _____ Date/Time to Plug: 12/19/17 / _____
 Plug Co License No.: 3097 Plug Co. Name: K-W OIL WELL SERVICES, INC.
 Proposal Revd from: Jim Kepley Company Name: K-W Phone: (620) 431-2285

Proposed
Plugging
Report:

Fill well with portland cement from TD to surface.

Plugging Proposal Received By: Frank Guilfoyle Witness Type: COMP - Complete 100%
 Date/Time Plugging Completed: 12/19/17 / _____ KCC Agent: Frank Guilfoyle

Actual Plugging Report:	Perfs:	Top	Bottom	Thru
Well was buried. Dig out and set 10" surface to bring above ground. Perforate casing. Run 1" and wash to 500 ft. Pump Portland cement to surface. Pull pipe and top off well. Pump total of 32 sacks of cement. Well plugged.		<u>100</u>	<u>300</u>	<u>CSG - Casing</u>

Remarks: Contract No. 43084. Control No. 20170025-001. GPS'ed by FG. Reg Sec.

Plugged Thru: TBG - Tubing Plugged Due to Compliance Issue: ☐ Yes ☐ No

District: 03

KCC WICHITA
APR 05 2018
RECEIVED

Frank Guilfoyle
 (Technician)

Form: District Plugging Report - _____