

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging of formations.

Give All Information Completely  
Make Required Affidavit  
or Driller Report to:  
Conservation Division  
State Corporation Commission  
Biting Building  
W. 11th, Kansas

Barton County Sec. 34 Twp. 20 Rge. 13 (E) (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE SW  
 Lease Owner B & R Drilling, Inc.  
 Lease Name Tucker Well No. 1  
 Office Address Russell, Ks.  
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
 Date well completed 3/11 1949  
 Application for plugging filed 3/10 - Verbally 1949  
 Application for plugging approved 3/10 - Verbally 1949  
 Plugging commenced 3/10 1949  
 Plugging completed 3/11 1949  
 Reason for abandonment of well or producing formation \_\_\_\_\_

NORTH


Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3650 Feet  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				<u>8 5/8"</u>	<u>166'</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plug at 164'. 15 Sacks cement. Fill with mud to 30'. Plug and 10 sacks cement.

**RECEIVED**  
 Conservation Div.  
 MAR 18 1949  
 STATE CORPORATION  
 COMMISSION  
 KANSAS

3-16-49

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to B & R Drilling, Inc.  
 Address Russell, Ks.


STATE OF KANSAS, COUNTY OF RUSSELL, ss.  
C. L. Roberts (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. L. Roberts

Russell, Ks. (Address)

SUBSCRIBED AND SWORN to before me this 15th day of March, 1949

My commission expires 6/17/50 Notary Public.



Tucker #1  
B & R Drilling, Inc.

Sec. 34 Twp. 20 Rge. 13  
Barton County, Kansas

Total Depth: 3650  
Comm: 2/22/49  
Comp: 3/11/49

Casing  
8 5/8" Set @ 166'

Cement  
200 Sacks

Formation: Depth:

Sand, Gravel & Clay	115
Iron & Lime	130
Clay, Shale & Shells	165
Shale & Shells	218
Sand	250
Shale, Sand & Pyrite	278
Red Rock & Sand	459
Red Bed & Shells	560
Red Rock & Shale	860
Red Bed	1135
Shale & Shells	1232
Salt & Shale	1435
Salt & Shale	1570
Shale & Shells	1610
Anhydrite & Shale	1632
Shale & Shells	1635
Lime	1725
Lime & Shale	1850
Sandy Lime	1940
Lime	2025
Broken Lime & Pyrite	2085
Lime & Shale	2195
Shale	2290
Lime & Shale	2570
Shale	2670
Lime & Shale	2830
Lime	3240
Lime & Shale	3285
Lime	3490
Lime & Shale	3522
Sand	3525
Conglomerate	3540
Conglomerate Cherty	3560
Conglomerate	3615
Lime	3650

RECEIVED  
Consent to Drill  
MAR 16 1949  
STATE CORPORATION  
COMMISSION  
KANSAS

STATE OF KANSAS)  
RUSSELL COUNTY ) SS

I hereby certify that the above information is true and correct  
to the best of my knowledge.

Mary Lois Kabin

Subscribed and sworn to before me this 15th day of March, 1949.

Clara L. Sumner  
Notary Public

My Commission Expires 6/17/50

PLUGGING  
FILE SEC 34 T 20 R 13W  
BOOK PAGE 86 LINE 3 V