


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

Barton County. Sec. 26 Twp. 20S Rge. 13W(E) (W)  
Location as "NE/CNW/SW" or footage from lines SW SW SE  
Lease Owner ALPINE OIL & ROYALTY CO., INC.  
Lease Name DENBO "B" Well No. 1  
Office Address 800 Bitting Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) dry hole  
Date well completed June 17, 1961 19  
Application for plugging filed June 17, 1961 19  
Application for plugging approved June 17, 1961 19  
Plugging commenced June 17, 1961 19  
Plugging completed June 17, 1961 19  
Reason for abandonment of well or producing formation non-productive in commercial quantities  
If a producing well is abandoned, date of last production \_\_\_\_\_ 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

NORTH



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Donald Truan  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3572 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	205	cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Heavy mud \* from total depth of 3572 feet to 200 feet; 1/4 sack hulls and plug; 25 sacks cement through drill pipe; mud to 40 feet; xxx 1/2 sack hulls and plug; 10 sacks cement and 2 sacks cement in rat hole

RECEIVED  
STATE CORPORATION COMMISSION

MAR 26 1963

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Quaker Drilling Co., Inc.  
Address 800 Bitting Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Thomas M. McCaul (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Thomas M. McCaul  
800 Bitting Building, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 18th day of July, 1961

My commission expires August 10, 1961  
Virginia M. ... Notary Public.

## WELL LOG

ALPINE OIL &amp; ROYALTY CO., INC.

Commenced: June 9, 1961

Contractor: Quaker Drilling Co., Inc.

Completed: June 17, 1961

Clarence Denbo No. 1-B  
SW SW SE Sec. 26-20S-13W  
Barton County, Kansas

Elevation: 1878 K. B.

Production: E. &amp; A.

## Casing Record:

Set 8 5/8 inch casing at 205 feet with 225 sacks cement

(Figures Indicate the Bottom of the Formation)

<u>FORMATION</u>	<u>DEPTH</u>	<u>FORMATION TOPS</u>	
Sand	145	Heebner	3134 -1258
Hard Sand	147	Brown Lime	3255 -1379
Sand	160	Lansing	3269 -1393
Sahel	205	Conglomerate	3503 -1627
Sand, Shale & Red Bed	705	Rotary Total	
Anhydrite	730	Depth	3572 -1694
Shale	975		
Shale and Lime Shells	1555		
Lime and Shale	1790		
Sandy Lime and Shale	2420		
Shale and Lime	3336		
Lime	3410		
Lime and Shale	3572		

RECEIVED  
CORPORATION COMMISSION

MAR 26 1963

CONSERVATION DIVISION  
Wichita, Kansas

We hereby certify the foregoing to be a true and correct copy of the Driller's Log of the well drilled in the SW SW SE of Section 26, Township 20 South, Range 13 West, Barton County, Kansas.

QUAKER DRILLING CO., INC.

By: Thomas M. M. Carl

Subscribed and Sworn to before me a Notary Public this 1st day of August, 1961.

Virginia Mundell  
Virginia Mundell, Notary Public

MY COMMISSION EXPIRES:  
August 10, 1961