


WELL PLUGGING RECORD

Give All Information Completely
Make Return Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Barton County. Sec. 26 Twp. 20S Rge. 13W (E) (W)
Location as "NE/CNW%SW%" or footage from lines SE SE SW
Lease Owner ALPINE OIL & ROYALTY CO., INC.
Lease Name C. DENBO Well No. 1
Office Address 800 Bitting Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil well
Date well completed April 20, 1961 19
Application for plugging filed March 1, 1963 19
Application for plugging approved March 1, 1963 19
Plugging commenced March 3, 1963 19
Plugging completed March 6, 1963 19
Reason for abandonment of well or producing formation
non-productive in commercial quantities
If a producing well is abandoned, date of last production May 18 1962
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Don Truan
Producing formation Lansing-KC Depth to top 3267 Bottom 3570 Total Depth of Well 3570 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	202	cemented
				5 1/2"	3569	2800 ft.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set plug at 3280 feet, ran 4 sacks of cement from 3280 feet to 3260 feet; mudded from 3260 feet to 205 feet, rock bridge 205' to 195 ft. and 6 sacks of cement from 195 to 175 feet. 19 sacks of cement from 175 ft. to 120 ft., mudded from 120 ft. to 40 ft. and rock and 10 sacks of cement from 40 ft. to base of cellar

RECEIVED
STATE CORPORATION COMMISSION
MAR 26 1963
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Glenn and Smith Pipe Pulling Company
Address Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Thomas M. McCaul (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Thomas M. McCaul
800 Bitting Building, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 13th day of March 1963

My commission expires August 10, 1965
Virginia Mundell Notary Public.

WELL LOG

ALPINE OIL & ROYALTY CO., INC.

Commenced: April 11, 1961

Contractor: Quaker Drilling Co., Inc.

Completed: April 20, 1961

Clarence Denbo No. 1
SE SE SW Sec. 26-20S-13W
Barton County, Kansas

Elevation: 1880 K. B.

Casing Record:

Set 8 5/8" casing at 202 feet with 225 sacks cement
Set 5 1/2" casing at 3569 feet with 150 sacks cement

(Figures Indicate the Bottom of the Formations)

<u>FORMATION</u>	<u>DEPTH</u>	<u>FORMATION TOPS</u>	
Sand	126	Heehner	3134 -1254
Hard Sand	143	Brown Lime	3254 -1374
Blue Shale	203	Lansing	3267 -1387
Blue Shale and Shells	300	Base of Kansas	
Red Bed	714	City	3498 -1618
Anhydrite	735	Conglomerate	3512 -1637
Shale and Shells	1610	Rotary Total	
Lime and Shale	1860	Depth	3570 -1690
Sandy Lime and Shale	2020		
Shale and Lime	2145		
Shale	2270		
Shale and Shells	2470		
Shale and Lime	2890		
Lime	2976		
Lime and Shale	3245		
Lime	3300		
Lime and Shale	3362		
Lime	3385		
Lime and Shale	3440		
Lime	3510		
Lime and Cherty Shale	3560		
Conglomerate	3570		

RECEIVED
STATE CORPORATION COMMISSION

MAR 4 1963

CONSERVATION DIVISION
Wichita, Kansas

We hereby certify the foregoing to be a true and correct copy of the Driller's Log of the well drilled in the SE SE SW of Section 26, Township 20 South, Range 13 West, Barton County, Kansas.

QUAKER DRILLING CO., INC.

By: 

SUBSCRIBED AND SWORN TO before me a Notary Public this 8th day of August 1961.

MY COMMISSION EXPIRES:
August 10, 1961
Virginia Mundell, Notary Public