

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15.009.02027.0001

LEASE NAME M. Lonnon B #3

WELL NUMBER _____

SPOT LOCATION NE SE SE/4

SEC. 25 TWP. 20 SRGE. 13 W (E) or (W)

COUNTY Barton

Date Well Completed _____

Plugging Commenced 3/8/84

Plugging Completed 3/12/84

LEASE OPERATOR Southern States Oil Co.

ADDRESS 2121 S. Columbia, Suite 410 Tulsa, Ok. 74114

PHONE # () _____ OPERATORS LICENSE NO. # 5354

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom T.D. 3565'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	253'	none
				5 1/2"	3564'	127.25'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Ran sand to 3170' & 5 sacks cement. Pipe parted. Pulled 4 joints. Plugged well with 250 sacks cement.

Plugging complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

RECEIVED

STATE CORPORATION COMMISSION

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

MAR 19 1984

CONSERVATION DIVISION
Wichita, Kansas

My Commission expires: _____



SUBSCRIBED AND SWORN TO before me this 16th day of March, 1984

Irene Hoover
Notary Public

15.009.02027.0000

M. LONNOR 843 - NE SE SE 1/4 Section 25-20-13 Barton Co., Kansas
 Company - Virginia Drlg Co Inc.
 Commenced - May 8, 1961
 Completed - July 6, 1961
 Elevation - 1862 KB
 T. D. - 3565

8 5/8" set at 253' w/230 ex cem.
 5 1/2" set at 3564 w/75 ex cem.

FORMATION	DEPTH
Sand	0- 190
Shale & sand	190- 250
Red bed	250- 675
Anhydrite	675- 700
Shale & shells	700-1215
Salt	1215-1500
Shale & shells	1500-1550
Lime & Shale	1550-2000
Shale & Shells	2000-2745
Lime & Shale	2745-3360
Lime	3360-3470
Cong. & lime	3470-3480
Arbuckle	3480-3565 TD

TOPS:
 3091 - Heebner
 3214 - Brn lime
 3229 - Lansing
 3449 - Cher Cong.
 3485 - Arbuckle

6/20/61 - 2 bbls. acid
 21 500 gals.

Perf. 24 holes 3496-3502

min. well.

S. A. Murphy
 S. A. Murphy

Subscribed and sworn to before me, a notary public,
 this 18th day of July 1961.

Marcel Hawlin
 Notary Public

My commission expires: Febr. 5, 1965.

RECEIVED
 STATE CORPORATION COMMISSION

MAR 02 1964

CONSERVATION DIVISION
 Wichita, Kansas