


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas



Locate well correctly on above Section Plat

Barton County, Sec. 25 Twp. 20S Rge. 13W(E) (W)
Location as "NE/CNW/SW" or footage from lines NE NW SW
Lease Owner ALPINE OIL & ROYALTY CO., INC.
Lease Name Edna May Denbo Well No. 2
Office Address 800 Bitting Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry-Hole) dry hole
Date well completed December 2, 1961 19
Application for plugging filed December 2, 1961 19
Application for plugging approved December 2, 1961 19
Plugging commenced December 2, 1961 19
Plugging completed December 2, 1961 19
Reason for abandonment of well or producing formation non-productive in commercial quantities
If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Donald Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3560 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	220	cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud from total depth - 3560 feet to 210 feet; 1/3rd sack hulls and 25 sacks cement through drill pipe; mud to 40 feet; 1/2 sack hulls and cement to bottom of cellar - 2 sacks cement in rat hole

RECEIVED
STATE CORPORATION COMMISSION
DEC 6 1961

CONSERVATION DIVISION
Wichita, Kansas

12-6-61

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Quaker Drilling Co., Inc.
Address 800 Bitting Building, Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.
Thomas M. McCaul

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Thomas M. McCaul

800 Bitting Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of December, 19 61

Ervin M. Muddell
Notary Public.

My commission expires August 10, 1965

WELL LOG

ALPINE OIL & ROYALTY CO., INC.

Commenced: November 25, 1961

Contractor: Quaker Drilling Co., Inc.

Completed: December 2, 1961

Edna May Denbo No. 2
NE NW SW Sec. 25-20S-13W
Barton County, Kansas

Elevation: 1864 K.B.

Casing Record:

Set 8 5/8 inch casing at 220 feet with 250 sacks cement

(Figures Indicate the Bottom of the Formations)

<u>FORMATION</u>	<u>DEPTH</u>	<u>FORMATION TOPS</u>	
Surface Soil and Sand	160	Heebner	3099 -1235
Shale	300	Brown Lime	3221 -1357
Red Bed	698	Lansing	3235 -1371
Anhydrite	723	Conglomerate	3465 -1600
Shale and Shells	1180	Arbuckle	3516 -1652
Lime and Shale	2055	Rotary Total	
Shale and Streaks of Lime	2260	Depth	3560 -1696
Shale and Lime	3030		
Lime	3105		
Shale and Lime	3315		
Lime	3400		
Lime and Shale	3455		
Chert, Lime and Shale	3516		
Dolomite	3560		

RECEIVED
STATE CORPORATION COMMISSION

DEC 6 1961

CONSERVATION DIVISION
Wichita, Kansas

We hereby certify the foregoing to be a true and correct copy of the Driller's Log of the well drilled in the NE NW SW of Section 25, Township 20 South, Range 13 West, Barton County, Kansas.

QUAKER DRILLING CO., INC.

By: 
Thomas M. McCaul, President

SUBSCRIBED AND SWORN TO before me a Notary Public this 6th day of December, 1961.

MY COMMISSION EXPIRES:
August 10, 1965


Virginia Mundell, Notary Public