

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Barton County, Sec. 25 Twp. 20S Rge. 13 (E) W (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW SW SE

Lease Owner ALPINE OIL & ROYALTY CO., INC. - Parks & Ryder

~~300 Bitting Building~~ 300 Bitting Building Well No. 1

~~Owner~~ Lease Name: Leonen LONNAN

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 10-1- 19 50

Application for plugging filed 10-2 19 50

Application for plugging approved 10-2 19 50

Plugging commenced 10-2 19 50

Plugging completed 10-2 19 50

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough

Producing formation Conglomerate Depth to top 3464 Bottom 3509 Total Depth of Well 3509 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	256'	Cemented.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud from Total Depth to 3509 feet to 256 feet. Solid plug and 15 sacks cement. Mud to 35 feet. solid plug and 10 sacks cement to surface.

RECEIVED
STATE CORPORATION COMMISSION
OCT 5 - 1950
CONSERVATION DIVISION
Wichita, Kansas
10-5-50

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to:
Address Alpine Oil & Royalty Co., Inc. 300 Bitting Building, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Thomas M. McCaul (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Thomas M. McCaul

300 Bitting Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 4th day of October, 19 50.

My commission expires August 8, 1953 Leon Allen Notary Public.

PLUGGING
FILE REC 25 T 20 1950
BOOK PAGE 32 11410

WELL LOGALPINE OIL & ROYALTY CO., INC.
Parks and Ryder, et al

Elevation: 1864 R.B.

Commenced: 9-21-50

Completed: 10-1-50

Contractor: Quaker Drilling Co., Inc.

Production: D & A

Lonnon No. 1
SW SW SE Sec. 25-20S-13W
Barton County, Kansas

Casing Record:

Set 8 5/8" at 256 feet with 225 sacks cement.

(Figures Indicate Bottom of Formations)

<u>FORMATION</u>	<u>DEPTH</u>	<u>FORMATION TOPS</u>	
Surface Clay and Sand	185	Heebner	3098 -1234
Shale	256	Brown Lime	3217 -1353
Red Bed and Shale	682	White Lime	3230 -1366
Anhydrite	712	Conglomerate	3464 -1600
Shale and Shells	1020	Total Depth	3509 -1645
Shale and Lime	1590		
Lime	1870	D & A	
Lime and Shale	2200		
Shale	2535		
Lime and Shale	2905		
Lime	3115		
Lime and Shale	3380		
Lime	3435		
Lime and Shale	3464		
Conglomerate	3509 TD		

RECEIVED
STATE CORPORATION COMMISSION
OCT 5 - 1950
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above is a true and correct copy of Driller's Log of well drilled in the SW SW SE of Section 25, Township 20 South, Range 13 West, Barton County, Kansas.

ALPINE OIL & ROYALTY CO., INC.

By: Donald M. McLaughlin
PresidentSubscribed and sworn to before me this 4th day of October, 1950.L. J. Amos
Notary PublicMy commission expires:
August 8, 1953.