

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
207 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-009-23,411-0000

LEASE NAME Ralph Phillips #1

WELL NUMBER \_\_\_\_\_

SPOT LOCATION C W/2 SE NW

SEC. 25 TWP. 20 S RGE. 13 W (E) or (W)

COUNTY Barton

Date Well Completed \_\_\_\_\_

Plugging Commenced 12/3/84

Plugging Completed 12/10/84

LEASE OPERATOR D. R. Lauck Oil Co., Inc.

ADDRESS 221, S. Broadway, Suite 400, Wichita, Ks. 67202

PHONE # ( ) \_\_\_\_\_ OPERATORS LICENSE NO. \_\_\_\_\_

Character of Well \_\_\_\_\_  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3640'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size   | Put In | Pulled out |
|-----------|---------|------|----|--------|--------|------------|
|           |         |      |    | 8 5/8  | 334'   | none       |
|           |         |      |    | 5 1/2" | 3639'  | 2837'      |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged bottom with 5 sacks cement, sand to 3350' & 5 sacks cement. Shot pipe at 2930' and 2837'. Pulled 91 joints of pipe. Plugged well with 4 hulls, 25 cement, 12 gel, 40 cement, 3 gel, 1 hull, & 100 sacks 50/50 poz 6% gel 3% c.c.

Plugging complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, Ks. 67524

STATE OF Kansas

COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 17th day of December, 1984



My Commission expires: \_\_\_\_\_

Irene Hoover  
Notary Public

D. R. Lauck Oil Company, Inc. - Ralph Phillips #1  
 221 S. Broadway, Suite 400 C W/2 SE NW Sec. 25-20S-13W  
 Wichita, Kansas 67202 Barton County, Kansas

Contractor: D. R. Lauck Oil Company, Inc.  
 221 S. Broadway, Suite 400  
 Wichita, Kansas 67202

Commenced: January 16, 1984  
 Completed: January 25, 1984

Drillers Log

|                   |          |
|-------------------|----------|
| Sand & Top Soil   | 104      |
| Sand & Gray Shale | 337      |
| Red Bed           | 575      |
| Red Bed & Shale   | 685      |
| Anhydrite         | 705      |
| Shale             | 1690     |
| Shale & Shells    | 2108     |
| Shale             | 2160     |
| Shale & Shells    | 2675     |
| Shale & Lime      | 2925     |
| Shale             | 3125     |
| Shale & Lime      | 3275     |
| Lime              | 3640 RTD |

Casing: 334' 8-5/8" cemented with 130 sacks Light Cement,  
 50 sacks Common Cement, 3% Calcium Chloride.  
 3639' 5-1/2" cemented with 125 sacks 60-40 Pozmix Cement,  
 10% Salt, 500# Salt Flush run ahead of cement.

RECEIVED  
 STATE CORPORATION COMMISSION

JUN 12 1984

CONSERVATION DIVISION  
 Wichita, Kansas