


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Barton County, Sec. 25 Twp. 20 Rge. (E) 13 (W)

Location as "NE/CNW/SW" or footage from lines NW NE SW
Lease Owner Leben Drilling, Inc.
Lease Name Edna May Denbo Well No. 1
Office Address Box 486, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed _____ 19____
Application for plugging filed August 21 1969
Application for plugging approved _____ 19____
Plugging commenced August 30 1969
Plugging completed September 5 1969
Reason for abandonment of well or producing formation depleted



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Donald Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3549 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	222'	8 5/8"	222'	none
		0	3548'	5 1/2"	3548'	2633.25

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pushed plug to 3380', set 10' sand bridge and dumped 5 sacks cement.
Squeezed well with 20 sacks mud and 90 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
SEP 23 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor PIPE PULLERS, INC.
Address Box 486, Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Evelyn Roth (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Evelyn Roth
Ellinwood, Kansas

SUBSCRIBED AND SWORN to before me this 22nd day of September, 1969

My commission expires July 7, 1972
J. R. Rader Notary Public.

15.009.61219.0000
 RECEIVED
 STATE CORPORATION COMMISSION
 AUG 22 1969
 CONSERVATION DIVISION
 Wichita, Kansas

R

WELL LOG

ALPINE OIL & ROYALTY CO., INC.

Commenced: May 3, 1961

Contractor: Quaker Drilling Co., Inc.

Completed: May 11, 1961

Edna May Denbo No. 1
 NW NE SW Sec. 25-20S-13W
 Barton County, Kansas

Elevation: 1864 K. B.

Casing Record:

Set 8 5/8 inch casing at 222 feet with 200 sacks cement
 Set 5 1/2 inch casing at 3548 feet with 150 sacks cement

(Figures Indicate the Bottom of the Formations)

<u>FORMATION</u>	<u>DEPTH</u>	<u>FORMATION TOPS</u>	
Sand	155	Heebner	3095 -1231
Shale	222	Brown Lime	3218 -1354
Red Bed, Shale & Sand	683	Lansing	3233 -1369
Anhydrite	709	Base of Kansas City	3455 -1591
Red Bed	730	Conglomerate	3462 -5198
Shale and Shells	1200	Arbuckle	3505 -1641
Shale	1510	Rotary Total Depth	3549 -1685
Lime and Shale	1915		
Sandy Lime & Shale	2030		
Lime and Shale	3310		
Lime	3325		
Lime and Shale	3399		
Lime	3505		
Dolomite and Chert	3549		

We hereby certify the foregoing to be a true and correct copy of the Driller's Log of the well drilled in the NW NE SW of Section 25, Township 20 South, Range 13 West, Barton County, Kansas.

QUAKER DRILLING CO., INC.

By: _____

SUBSCRIBED AND SWORN TO before me a Notary Public this 7th day of August, 1961

Virginia Mundell, Notary Public

MY COMMISSION EXPIRES:
 August 10, 1961

BRIDGE PLUG 3414

PERFS. 3396