

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15.009.01480.0000

API NUMBER N/A

LEASE NAME Swader

WELL NUMBER No. 1

2310' Ft. from S Section Line

990' Ft. from E Section Line

SEC. 29 TWP. 20S RGE. 13 (E) or (W)

COUNTY Barton

Date Well Completed 9-18-62

Plugging Commenced 4-20-87

Plugging Completed 5-04-87

LEASE OPERATOR Robinowitz Oil Company

ADDRESS 7130 S. Lewis, Suite 910, Tulsa, Oklahoma 74136

PHONE#(918) 481-7130 OPERATORS LICENSE NO. 6883

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? Yes If not, Is well log attached?

Producing Formation L-KC Depth to Top 3406' Bottom 3413' T.D. 3564'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
L-KC	Oil, Water	0	221	8 5/8	221	None
Arbuckle	Oil, Water	0	3548	5 1/2	3548	None
		2670	3666	4 1/2	996	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Set CIBP @ 3000'. Fill casing with 300 sacks of BJ 35% Dia-Mix Cement. Pump into 8 5/8" - 5 1/2" Annulus 50 sacks of cement blend mixed with 4 sacks of cottonseed hulls. WOC. Check cement top. Cut off casing and cap well. Restore location.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor BJ - Titan Services License No. _____

Address Box 200416 Houston, Texas 77216

STATE OF Oklahoma COUNTY OF Tulsa, ss.

C.J. Kliesner (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) C.J. Kliesner

(Address) 7130 S. Lewis, Ste 910, Tulsa, OK

SUBSCRIBED AND SWORN TO before me this 11th day of May, 19 87

My Commission Expires: May 22, 1988

Notary Public

MAY 14 1987

5-14-87