

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-24810-00-00
Spot: NWNESE Sec/Twnshp/Rge: 25-20S-13W
2500 feet from S Section Line, 450 feet from E Section Line
Lease Name: LONNON Well #: 2-25
County: BARTON Total Vertical Depth: 3695 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3588		150 SX
SURF	8.625	333		300 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/31/2018 1:00 PM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: KEVIN WILES SR Company: AMERICAN WARRIOR, INC. DBA Phone: (620) 272-1023

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement, 10 sx gel and 500 # hulls.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/31/2018 5:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1350', 675' and 300'. Ran tubing to 3400' and pumped 10 sx gel followed by 40 sx cement w/100 # hulls. Pulled tubing to 1400' and pumped 50 sx cement. Pulled tubing to 700'. Circulated cement to surface with 130 sx cement on casing and backside. Pulled tubing. Tied to casing and pressured to 250 psi with 40 sx cement. Shut in.

GPS: 38.28237 -098.70237

Perfs:

Top	Bot	Thru	Comments
3533	3537		

INVOICED
MAR 01 2018

Remarks: BASIC ENERGY SERVICES

Plugged through: TBG

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

CM

Received
KANSAS CORPORATION COMMISSION

FEB 05 2018

FEB 23 2018

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3