

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-009-22001-00-00  
Spot: SWSESE Sec/Twnshp/Rge: 27-19S-11W  
330 feet from S Section Line, 990 feet from E Section Line  
Lease Name: LEROY Well #: 4  
County: BARTON Total Vertical Depth: 3333 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: PO BOX 399  
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3332		125 SX
SURF	8.625	247		160 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/01/2018 1:00 PM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: KEVIN WILES SR Company: AMERICAN WARRIOR, INC. DBA Phone: (620) 272-1023

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement, 10 sx gel and 500 # hulls.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 02/02/2018 5:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1300', 530' and 250'. Ran tubing to 3200' and pumped 10 sx gel followed by 40 sx cement w/100 # hulls. Pulled tubing to 1300' and pumped 50 sx cement. Pulled tubing to 550' and pumped 210 sx cement. Had circulation with no cement to surface. Shut down for the day. 02/02/2018 - Tagged cement at 1240' with sand line. Ran tubing to 1020' and pumped 200 sx cement. Circulated cement to surface on casing and backside. Pulled tubing and topped off with 15 sx cement.

GPS: 38.36271 -098.52068

Perfs:

Top	Bot	Thru	Comments
3226	3230		
3130	3140		

Remarks: BASIC ENERGY SERVICES

Plugged through: TBG

District: 04

Signed Bruce Rodie  
(TECHNICIAN)

CM

INVOICED  
MAR 01 2018

FEB 05 2018