

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-24416-00-00
Spot: NWSWSWSW Sec/Twnshp/Rge: 4-31S-5E
500 feet from S Section Line, 150 feet from W Section Line
Lease Name: DIANE Well #: 1
County: COWLEY Total Vertical Depth: 3433 feet

Operator License No.: 33982
Op Name: ALTON OIL LLC
Address: PO BOX 117
WINFIELD, KS 67156

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2440		
CIBP		3300		
PROD	5.5	3433	1008	100 SX
SURF	8.625	202		125 SX
T1	2.375	3402		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/03/2018 8:00 AM
Plug Co. License No.: 34879 Plug Co. Name: CANAAN WELL SERVICE INC.
Proposal Rcvd. from: MICHAEL A. PRESSNALL Company: _____ Phone: (620) 221-4268

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 02/08/2018 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

DUMP BAILED 2 SX CEMENT ON TOP OF CIBP SET @ 3300'. RIH ON WIRELINE SET CIBP @ 2440', DUMP BAILED 2 SX CEMENT ON TOP OF PLUG. CUT CASING @ 1008', LAYED DOWN 25 JTS 5 1/2" CASING (1,008'). RIH WITH TUBING @ 255', QES ESTABLISHED CIRCULATION, MIXED AND PUMPED 100 SXS 60/40 POZMIX 2% CC TO SURFACE. CEMENT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
3381	3382	CSG	
3380	3381	CSG	
3379	3382	CSG	
2450	2462	CSG	

INVOICED
MAR 01 2018

Remarks: QES CEMENT TICKET #55293.

Plugged through: TBG

District: 02

Signed DUANE KRUEGER
(TECHNICIAN)

VK