

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-19445-00-00
Spot: NESENW Sec/Twnshp/Rge: 23-31S-5E
3630 feet from S Section Line, 2970 feet from E Section Line
Lease Name: SU-OLYMPIC MOORE Well #: 1
County: COWLEY Total Vertical Depth: 2350 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2348		75 SX
SURF	8.625	202		135 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/07/2018 8:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: R. A. (DICK) SCHREMMER Company: _____ Phone: (316) 524-1225

Proposed
Plugging
Method:

AS PER KCC RULES & REGS/ CIBC @ 2280' W/2 SXS. PERFORATE & CIRCUALTE 250'-0'.

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL
Date/Time Plugging Completed: 02/07/2018 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SET CIBP @ 2280', DUMP BAILED 2 SXS CEMENT ON TOP OF PLUG, LOADED HOLE & PRESSURED CASING. HELD OK. PERFORATED SQUEEZE HOLES 250'-251' (4 HOLES). SWEDGED INTO 4 1/2" CAISNG, MIXED & PUMPED 130 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCUALTED. CEMENT TICKET #45035.

Perfs:

Top	Bot	Thru	Comments
2314	2324	CSG	

Remarks: DENIED TA

Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN)

INVOICED
MAR 01 2018

JK