

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-19443-00-00
Spot: SESENNENW Sec/Twnshp/Rge: 24-32S-4E
1013 feet from N Section Line, 2940 feet from E Section Line
Lease Name: SHANNON, MARGARET Well #: 7
County: COWLEY Total Vertical Depth: 3034 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	6.625	2971		40 SX
SURF	8.25	2504		40 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/23/2018 8:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: R. A. (DICK) SCHREMMER Company: _____ Phone: (316) 524-1225

Proposed Plugging Method: AS PER KCC RULES & REGS/ 50 SXS 2 2970' PERF & CIRCULATE 250'-0'.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 01/23/2018 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TUBING @ 2970', COPELAND ACID MIXED & PUMPED 50 SXS CLASS A 3% CC & 75# HULLS & DISPLACED IN CASING. TAGGED CEMENT @ 2855'. PERFORATED SQUEEZE HOLES @ 260'-261' (4 HOLES). RIH W/TUBING @ 256', COPELAND ACID MIXED & PUMPED 100 SXS 60/40 POZMIX 4% GEL 2% CC TO SURFACE. CEMENT CIRCUALTED. LAYED DOWN TUBING. TOPPED WELL BACK TO SURFACE W/20 SXS. CEMENT TICKET #45022.

Perfs:

Top	Bot	Thru	Comments
2971	3034	OH	

INVOICED
MAR 01 2018

Remarks: DENIED TA

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER

(TECHNICIAN)

1/2