

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-19481-00-00
Spot: NESESE Sec/Twnshp/Rge: 27-31S-5E
990 feet from S Section Line, 330 feet from E Section Line
Lease Name: SU-BRYCE L RISING Well #: 1
County: COWLEY Total Vertical Depth: 2322 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2313		125 SX
SURF	8.625	218		150 SX

Well Type: OIL UIC Docket No: Date/Time to Plug: 02/07/2018 8:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: R. A. (DICK) SCHREMMER Company: Phone: (316) 524-1225

Proposed Plugging Method: AS PER KCC RULES & REGS. CIBP @ 2280 W/2 SXS PERF & CIRCULATE 260'-0'.

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 02/07/2018 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE SET CIBP @ 2280', DUMP BAILED 2 SXS CEMENT ON TOP OF PLUG. LOADED HOLE & PRESSURED CASING. HELD OK. RIH PERFORATED SQUEEZE HOLES 260'-261' (4 HOLES). SWEDGED INTO 4 1/2" CASING, COPELAND MIXED & PUMPED 110 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. CEMENT TICKET #45034.

Perfs:

Top	Bot	Thru	Comments
2313	2322	OH	

INVOICED
MAR 01 2018

Remarks: DENIED TA

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER

(TECHNICIAN)