

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-065-21036-00-00  
Spot: NESWNW Sec/Twnshp/Rge: 2-10S-25W  
3630 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: BERNARD LEASE Well #: 5  
County: GRAHAM Total Vertical Depth: 4051 feet

Operator License No.: 34318

Op Name: BEREXCO LLC

Address: 2020 N. BRAMBLEWOOD  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4048		450 SX
SURF	8.625	211		150 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 02/07/2018 9:30 AM

Plug Co. License No.: 34318

Plug Co. Name: BEREXCO LLC

Proposal Rcvd. from: MARK LEIKER

Company: BEREXCO LLC

Phone: (316) 772-8649

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/500 # hulls.  
Production perforations: 3777' - 3998'. Retainer stuck at 3924'.  
Casing leak at 1800' - 1801'.  
DV Tool set at 2168' w/500 sx cement. Did not circulate.

Plugging Proposal Received By: CASE MORRIS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 02/07/2018 1:00 PM

KCC Agent: PAT BEDORE

Actual Plugging Report:

Perfs:

Ran tubing to 3923' and pumped 130 sx cement w/300 # hulls. Pulled tubing to 2001' and pumped 65 sx cement w/200 # hulls. Pulled tubing to 984' and pumped 65 sx cement to circulate cement to surface. Pulled all tubing. Topped off 4 1/2" casing with 15 sx cement. Hooked to 8 5/8" x 4 1/2" annulus and pumped 20 sx cement with 150 psi. Leaking around casing head. Shut in pressure 150 psi.

GPS: 39.21528N -100.08488W

Remarks: GLOBAL CEMENT TICKET # 3287

Plugged through: TBG

District: 04

Signed

Pat Bedore  
(TECHNICIAN)

CM

Received  
KANSAS CORPORATION COMMISSION

FEB 09 2018

FEB 23 2018

CONSERVATION DIVISION  
WICHITA, KS

Form CP-2/3

INVOICED  
MAR 01 2018