

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-035-19469-00-00  
Spot: SWNENE Sec/Twnshp/Rge: 26-31S-5E  
4290 feet from S Section Line, 990 feet from E Section Line  
Lease Name: SU-SHANNON A Well #: 2  
County: COWLEY Total Vertical Depth: 2368 feet

Operator License No.: 4419  
Op Name: BEAR PETROLEUM, LLC  
Address: PO BOX 438  
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2366		100 SX
SURF	8.625	204		100 SX

Well Type: OIL UIC Docket No: Date/Time to Plug: 02/01/2018 8:00 AM  
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC  
Proposal Rcvd. from: R. A. (DICK) SCHREMMER Company: Phone: (316) 524-1225

Proposed AS PER KCC RULES & REGS  
Plugging  
Method:

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL  
Date/Time Plugging Completed: 02/01/2018 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

4-9-65 HALLIBURTON ENERGY PUMPED 50 SXS (200 CU FT) 60/40 POZMIX ON BOTTOM. CEMENT TICKET #793970. 2-1-2018 TAGGED CEMENT PLUG @ 1960'. RIH ON WIRELINE PERFORATED SQUEEZE HOLES 255'-256' (4 HOLES). RIH W/TUBING @ 275', COPLAND ACID ESTABLISHED CIRCULATION, MIXED & PUMPED 110 SXS 60/40 POZMIX 2% GEL TO SURFACE. CEMENT CIRCULATED. CEMENT TICKET #45031.

Perfs:

Top	Bot	Thru	Comments
2326	2336	CSG	


INVOICED  
MAR 02 2018

Remarks: DENIED TA

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)