

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-035-00374-00-00  
Spot: NWSWNE Sec/Twnshp/Rge: 26-31S-5E  
3630 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: SU-SHANNON AB Well #: 1  
County: COWLEY Total Vertical Depth: 2327 feet

Operator License No.: 4419  
Op Name: BEAR PETROLEUM, LLC  
Address: PO BOX 438  
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	2275		
PROD	5.5	2318		75 SX
SURF	8.625	204		100 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/01/2018 8:00 AM  
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC  
Proposal Revd. from: R. A. (DICK) SCHREMMER Company: \_\_\_\_\_ Phone: (316) 524-1225

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 02/01/2018 11:30 AM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE SET CIBP @ 2275, DUMP BAILED 2 SXS CEMENT ON TOP OF PLUG. RIH PERFORATED SQUEEZE HOLES (4 HOLES) @ 255'-256'. RIH W/ TUBING @ 275', COPELAND ACID ESTABLISHED CIRCULATION, MIXED & PUMPED 125 SXS 60/40 POZMIX 2% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 11:30 AM 2-1-2018. CEMENT TICKET #45030.

Perfs:

Top	Bot	Thru	Comments
2318	2327	OH	

INVOICED  
MAR 02 2018

Remarks: DENIED TA

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER

(TECHNICIAN)

SK