

TO:  
 STATE CORPORATION COMMISSION  
 CONSERVATION DIVISION - PLUGGING  
 266 N. Main St., Ste. 220  
 Wichita, KS 67202-1513

API Well Number: 15-159-22190-00-00  
 Spot: SWNE Sec/Twnshp/Rge: 7-20S-9W  
3300 feet from S Section Line, 1980 feet from E Section Line  
 Lease Name: FOOTE Well #: 1  
 County: RICE Total Vertical Depth: 3327 feet

Operator License No.: 4419  
 Op Name: BEAR PETROLEUM, LLC  
 Address: PO BOX 438  
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	3250		
PROD	5.5	3325	220	SX
SURF	8.625	215	165	SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/25/2018 3:00 PM  
 Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC  
 Proposal Revd. from: R. A. (DICK) SCHREMMER Company: BEAR PETROLEUM LLC Phone: (316) 524-1225

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: B. J. HOPE Witness Type: PARTIAL  
 Date/Time Plugging Completed: 01/26/2018 12:00 PM KCC Agent: VIRGIL CLOTHIER

**Actual Plugging Report:**

MIRU, PULL TUBING. SET CIBP AT 3250' AND CAP WITH 4 SX'S CEMENT. PERFORATE AT 1250', 900', AND 265'. RUN TUBING TO 1250' AND PUMP 35 SX'S COMMON WITH 3% CC. PULL TUBING UP TO 900' AND WAIT 1.5 HRS. ATTEMPT TO TAG CEMENT, COULD NOT. RUN TUBING BACK DOWN TO 1250' AND PUMPED 35 MORE SX'S COMMON WITH 3% CC. PULLED TUBING OUT OF HOLE. CAME BACK ON 1-26-18 AND TAGGED CEMENT AT 1110'. RUN TUBING TO 900' AND PUMPED 35 SX'S COMMON WITH 3% CC, PULLED TUBING TO 265' AND CIRCUALTED 60-40 4% GEL CEMENT TO SURFACE FROM BOTH CASINGS. PULLED TUBING OUT AND TOPPED OFF.

**Perfs:**

Top	Bot	Thru	Comments
3267	3282	CSG	
3038	3046	CSG	
2224	2232	CSG	

INVOICED  
 MAR 02 2018

Remarks: COPELAND CEMENT #C-46262.

Plugged through: TBG

District: 02

Signed Virgil Clothier  
 (TECHNICIAN)

1/8