

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-25906-00-00
Spot: SENWSWSE Sec/Twnshp/Rge: 35-16S-13W
825 feet from S Section Line, 2062 feet from E Section Line
Lease Name: DRECO Well #: 1
County: BARTON Total Vertical Depth: 3400 feet

Operator License No.: 34917
Op Name: BICKLE ENERGIES LLC
Address: PO BOX 816
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3398	1710	180 SX
SURF	8.625	774		325 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/07/2018 10:00 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: MATT BICKLE Company: BICKLE ENERGIES LLC DBA Phone: (785) 639-1681

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Cut off casing at 1710' leaving 1688' of 5 1/2" casing in well.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/07/2018 3:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Set 5 1/2" CIB plug at 3270'. Spotted 2 sx cement on top. Cut casing at 1710'. Pulled casing to 1450' and pumped 125 sx cement w/300 # hulls. Pulled casing to 800' and pumped 40 sx cement w/100 # hulls. Pulled casing to 400' and pumped 50 sx cement w/100 # hulls. Pulled casing to 200' and pumped 40 sx cement. Circulated cement to pit. POOH. Removed braden head and topped off casing with 10 sx cement. Cellar stayed full.

GPS: 38.61155 -098.72752

Perfs:

Top	Bot	Thru	Comments
3343	3347		
3321	3326		

INVOICED
MAR 02 2018

Remarks: QUALITY CEMENTING TICKET # 702
Plugged through: CSG

District: 04

Signed Ray A. Dinkel
(TECHNICIAN) CM

Received
KANSAS CORPORATION COMMISSION

FEB 23 2018

CONSERVATION DIVISION
WICHITA, KS

FEB 16 2018