

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-195-22662-00-00
Spot: NENWSESE Sec/Twnshp/Rge: 24-15S-22W
1200 feet from S Section Line, 950 feet from E Section Line
Lease Name: CHERYL Well #: 1
County: TREGO Total Vertical Depth: 4330 feet

Operator License No.: 9860
Op Name: CASTLE RESOURCES, INC.
Address: PO BOX 583
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4329		350 SX
SURF	8.625	209		160 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/11/2018 9:30 AM
Plug Co. License No.: 99974 Plug Co. Name: GLOBAL CEMENTING
Proposal Rcvd. from: JERRY GREEN Company: CASTLE RESOURCES, INC. DBA Phone: (785) 625-5155

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/300 # hulls, and 1800# gel
Alt II Cemented with 350 sx CWC.
Perforations: 4248' - 4256' and 4270' - 4274'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/11/2018 1:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Tied on to casing and pumped 75 sx cement w/300 # hulls, followed by 18 sx gel, followed by 200 sx cement. Shut in pressure 1500 psi. Tied on to backside and squeezed with 75 sx cement. Shut in pressure 250 psi.

GPS: 38.72910 -099.71235

Perfs:

Top	Bot	Thru	Comments
4270	4274		
4248	4256		

Remarks: GLOBAL CEMENT TICKET # 3218

Plugged through: CSG

District: 04

Signed _____

Marvin Mills
(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

FEB 23 2018

CONSERVATION DIVISION
WICHITA, KS

C.M.

Form CP-2/3

redo - JAN 23 2018
Jan 11 2018

INVOICED
MAR 02 2018