

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-205-27775-00-01  
Spot: SENWNENW Sec/Twnshp/Rge: 22-30S-16E  
4723 feet from S Section Line, 3620 feet from E Section Line  
Lease Name: FORSLUND Well #: 22-1  
County: WILSON Total Vertical Depth: 944 feet

Operator License No.: 34769  
Op Name: CHEROKEENRG LLC  
Address: 112 SOUTH 5TH STREET P.O. BOX 111  
NEODESHA, KS 66757

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		685		
PROD	4.5	939		105 SX
SURF	8.625	22		8 SX

Well Type: GAS UIC Docket No: Date/Time to Plug: 02/16/2016 12:00 PM  
Plug Co. License No.: 31696 Plug Co. Name: CUNNINGHAM CRUDE, A GENERAL PARTNERSHIP  
Proposal Revd. from: PAM GRAVES Company: DAKOTA PRODUCTION CO., INC Phone: (620) 432-1840

Proposed Plugging Method: Pull rods and tubing from hole, run 1" to bottom, gel hole, pull up to 575', spot 10 sacks of cement, pull up to 225', cement to surface. Pull pipe out of hole and top off cement.

Plugging Proposal Received By: ALAN DUNNING WitnessType: NONE  
Date/Time Plugging Completed: 02/16/2016 12:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A 2.375 inch cement string was washed to 680 ft and the hole gelled. The cement string was pulled to 575 ft and 10 sacks of cement spotted. The cement string was pulled to 225 ft and the well filled to surface with 22 sacks of cement. A total of 32 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

Perfs:

Top	Bot	Thru	Comments
629	633		
612	633		

RECEIVED  
KCC DIST # 3  
FEB 28 2018  
CHANUTE, KS

AD

Remarks:

Plugged through: CSG

District: 03

Signed

Alan Dunning  
(TECHNICIAN)

Form CP-2/3