

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-22521-00-01
Spot: SWSESWNE Sec/Twnshp/Rge: 2-10S-21W
2958 feet from S Section Line, 1875 feet from E Section Line
Lease Name: KELLER-SUTOR Well #: 1
County: GRAHAM Total Vertical Depth: 3845 feet

Operator License No.: 3553
Op Name: CITATION OIL & GAS CORP.
Address: 14077 CUTTEN RD PO BOX 690688
HOUSTON, TX 77269

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3840		150 SX
SURF	8.625	206		135 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/06/2018 9:30 AM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: NEIL PFANNESTIEL Company: CITATION OIL & GAS CORP. DBA Phone: (281) 891-1555

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/400 # hulls.
Production perforations: 3822' - 3826'.
CIBP set at 3835'.
TOF at 2592' (39 joints of 2 7/8" tubing, 2 1/2" x 2 x 14' pump stuck in hole.)
Perforation and squeeze at 2190' w/425 sx cement.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/06/2018 12:15 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 2555' and pumped 125 sx cement. Pulled tubing to 1275' and pumped 140 sx cement w/400 # hulls to circulate cement to surface. Pulled all tubing. Hooked to 5 1/2" casing and pumped 15 sx cement. Shut in pressure 550 psi. Hooked to 8 5/8" x 5 1/2" annulus and pumped 10 sx cement. Shut in pressure 500 psi.

GPS: 39.21355N -099.63001W

Perfs:

Top	Bot	Thru	Comments
3822	3826		

Remarks: BASIC ENERGY SERVICES TICKET # 16426

Plugged through: TBG

District: 04

Signed _____

Pat Bedore

(TECHNICIAN)

CM

Received
KANSAS CORPORATION COMMISSION

FEB 23 2018

CONSERVATION DIVISION
WICHITA, KS

FEB 09 2018

Form CP-2/3

INVOICED
MAR 02 2018